

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit


Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Russell County. Sec. 25 Twp. 13 Rge. (E) 15 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE S/2 NW
Lease Owner. John Lindas
Lease Name. Strecker Well No. 1
Office Address. Union National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. 11-23 19.45
Application for plugging filed. 7-20- 19.47
Application for plugging approved. 7-20 19.47
Plugging commenced. 7-20 19.47
Plugging completed. 7-20 19.47
Reason for abandonment of well or producing formation. Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production. 19.
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. H. W. Kerr
Producing formation. Depth to top. Bottom. Total Depth of Well. 3114 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	234'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

The hole was filled with cement 3114' to 3075' 10 sacks heavy mud 3075' to 250' cement 250' to 205' 15 sax mud 205' to 15' cement into base of cellar 10 sax.

234' of 8 5/8" pipe cemented and left in hole.

JUL 25 1947
07-25-1947

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to C. L. Gabbert
Address. 2509 Shawnee Drive, Great Bend, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Scott Stuckey (employee of owner) or (owner/operating) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Scott Stuckey
1316 Union Natl Bank Bldg Wichita, KS
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of July, 1947.
Catherine Dancy Notary Public.

My commission expires March 25, 1948

PLUGGING
FILE SEC 25 T 13 R 15W
BOOK PAGE 121 LINE 39

John Lindas
Strecker #1

Sec. 25 Twp. 13 Rge. 15
County: Russell, Kansas

Total Depth: 3108'
Casing: 10/24/45 Casing: 11/23/45

Casing
10 Jts. 8 5/8" Set at 245'
100 Jts. 5 1/2" Set at 3088'

Cement
125 Sacks
100 Sacks

Formation:	Depth:
Surface Clay & Shale	15'
Shale	35
Shale & Shells, Sand	205
Shale	245
Shale & Shells	260
Sand & Shale	320
Shale & Shells	375
Sand & Iron	415
Hard Lime	435
Sand, Shale & Shells	660
Shale & Shells, Red Bed	940
Anhydrite	980
Shale & Shells	1375
Salt & Shale	1575
Shale & Shells	1655
Broken Lime	1730
Lime & Shale	1850
Lime	1885
Lime & Shale	1970
Shale	2010
Lime	2020
Lime & Shale	2045
Iron, Lime & Shale	2085
Broken Lime & Shale	2165
Lime & Shale	2445
Shale & Shells	2710
Lime & Shale	2879
Lime	3108


I hereby certify that the above information is true and correct to the best of my knowledge.

Clara Lummel

Subscribed and sworn to before me this 26th day of November, 1945.

My Comm. Expires 7/2/49

Jenevieve Poole
Notary Public



Cecil Burton
Box 112
G. B.

PLUGGING
FILE SEC 25 T 13 R 15 W
BOOK PAGE 121 LINE 22