

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form CP-4  
March 2009

Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

WELL PLUGGING RECORD  
K.A.R. 82-3-117

081 ke 40

OPERATOR: License #: 32446  
Name: Merit Energy Company  
Address 1: 13727 Noel Rd., Suite 500  
Address 2: \_\_\_\_\_  
City: Dallas State: TX Zip: 75240 + \_\_\_\_\_  
Contact Person: Lynne Moon /Regulatory Manager  
Phone: (972) 628-1569  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All! (If needed attach another sheet)  
Chester Depth to Top: 5430' Bottom: 5466' T.D. 5503'  
Morrow Depth to Top: 5272' Bottom: 5318' T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 081-10221-0001  
Spot Description: \_\_\_\_\_  
SE NE Sec. 29 Twp. 28 S. R. 34  East  West  
1980 Feet from  North /  South Line of Section  
660 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner: **ADD KCC**  
 NE  NW  SE  SW  
County: Haskell  
Lease Name: Stuckey (JDG) Well #: 1 - 29  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: 7/26/10 (Date)  
by: Jack Maclaskey (KCC District Agent's Name)  
Plugging Commenced: 7/26/10  
Plugging Completed: 7/28/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	1866'	NONE
		Production	5 1/2"	5502'	1947'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set 5 1/2" 10K CIBP @ 5222' & cap w/ 2 sks cement . Cut 5 1/2" casing @ 1947' , POH w/ 58 jts 5 1/2" csg . Run tbg @ 1896' & spot 80 sks Class "C" cement ( 18.8 bbl slurry ) up to 1601' , Pull up hole w/ tbg @ 680' , Mix & spot 50 sks Class "C" cement up to 500' , Top out 64' - 4' w/ 20 sks cement

RECEIVED  
AUG 05 2010

KCC WICHITA

Plugging Contractor License #: 33338 Name: ORR ENTERPRISES, INC.  
Address 1: P.O. Box 1706 Address 2: \_\_\_\_\_  
City: Duncan State: Oklahoma Zip: 73534 + 1706  
Phone: (580) 467-0258

Name of Party Responsible for Plugging Fees: MERIT ENERGY COMPANY  
State of TEXAS County, DALLAS, ss.  
LYNNE MOON  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Lynne Moon