

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Ellis County, Sec. 17 Twp. 11 Rge. 17W(E) (W) ~~SE SE NW~~ S2 N1W1W and CC

Location as "NE/CNW/SE/SW" or footage from lines  
Lease Owner Clinton Oil Company  
Lease Name Carmicheal #c 4 Well No. 4  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 6-21-1974  
Application for plugging filed 7-8-1974  
Application for plugging approved 7-11-1974  
Plugging commenced 8/26/74 19 74  
Plugging completed 8/28/74 19 74

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production Before acquiring 19       
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey  
Producing formation      Depth to top      Bottom      Total Depth of Well 34 Feet  
Show depth and thickness of all water, oil and gas formations. 3361'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				15 1/2"	35'	none
				10"	1096'	none
				7"	3352'	2197'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Checked hole, pushed plug to 3304', ran sand and 5 sacks cement. Shot pipe at 2303', 2202', pulled 69 joints. Set rock bridge from 365' to 350' and ran 7 yards ready mix.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 24 1974  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KELSO CASING PULLING  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE SS.  
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS  
(Address)

Subscribed and Sworn to before me this 31st day of August, 19 74

My commission expires       
MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

Margaret Melcher  
Notary Public.

15-051-02189-0001

THE DICKEY OIL COMPANY  
Carmichael-C No. 4

COMMENCED: 5-26-41  
COMPLETED: 6-21-41

LOCATION: C ~~1/4~~ ~~SE 1/4~~ ~~NW 1/4~~ 17-11-17  
Ellis County, Kansas  
ELEVATION: 1839

S2 NW NW ANB KC

Casing Record

35'  
1096'  
3352 1/2'

15 1/2"  
10"  
7"

LOG FROM DRILLING REPORTS

sand and shale	35
shale and shells	400
water sand	475
shale and shells	512
iron	530
shale and iron	590
water sand	730
red bed	1073
Top Anhydrite	1078
Anhydrite	1120
shale and shells	1460
salt and shale	1630
shale and shells	1788
broken lime	1850
shale	1898
shale and lime	1975
shale and shells	1990
lime	2086
broken lime	2200
shale and shells	2253
broken lime	2320
shale and shells	2800
Top Topeka	2800
Oil smell 2970-82	
lime	3126
top K.C. lime	3126
Strong Oil Smell 3139-46	
lime	3310
red bed	3330
conglomerate	3342
green shale	3352
sand	3354
top Arbuckle	3354
Arbuckle Lime	3361
F. D.	3361
Top Arbuckle corr. D.F.	3352 1/2

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 11 194  
CONSERVATION DIVISION  
Wichita, Kansas