

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

ELLIS County, Sec. 17 Twp. 11s Rge. (E) 17 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ -NE $\frac{1}{4}$ -SW $\frac{1}{4}$ -SW $\frac{1}{4}$

Lease Owner Champlin Refining Company

Lease Name Hadley "D" Well No. 11

Office Address P.O. Dr. #552, Enid, Oklahoma.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed September 16, 19 41

Application for plugging filed July 29, 19 51

Application for plugging approved August 6, 19 51

Plugging commenced July 30, 19 51

Plugging completed August 1, 19 51

Reason for abandonment of well or producing formation Non productive

If a producing well is abandoned, date of last production September 25, 19 50

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas.

Producing formation Arbuckle Depth to top 3466' Bottom Total Depth of Well 3750' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8" OD	1100'	None
				3 1/2" OD		
				4 1/2" OD	3467'	1541'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

Set cement plug in bottom from 3750' TD to 3425' then filled hole with heavy mud from top of ~~cement~~ cement to 1545' and set cement plug using 5 sacks of cement then filled hole with heavy mud from top of cement plug to 250' and set cement plug using 20 sacks of cement filling the hole from 250' to 190' then filled hole with heavy mud from 190' to 35' and set rock bridge and set cement plug in top of well from top of rock bridge to bottom of celler using 10 sacks of ~~some~~ cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Champlin Refining Company
Address P. O. Dr. #552, Enid, Oklahoma.

STATE OF Kansas, COUNTY OF Barton, ss.
S. P. Hall (employee of owner) or ~~Conservation Division~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. P. Hall
P. O. Box #167
Ellinwood, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of August, 19 51

My commission expires October 24, 1951

Notary Public. *M. Kenneth Stevins*

PLUGGING
FILE SEC 17 11 112
BOOK PAGE 120 LINE 29

AUG 9 X 1951
8-9-51

HADLEY D #11
 BURNETT POOL
 SW 1/4 Sec. 17 T11S R17W
 ELLIS COUNTY, KANSAS

FORMATION LOG

0'	-	315'	Shale & Shells
315'	-	570'	Shale & Shells
570'	-	605'	Shale
605'	-	825'	Shale
825'	-	1000'	Shale & Shells
1000'	-	1174'	Red Bed & Shale
1174'	-	1210'	Anhydrite.
1210'	-	1515'	Red Bed & Shale
1515'	-	1880'	Shale & Shells
1880'	-	2250'	Lime & Shale
2250'	-	2600'	Shale & Lime
2600'	-	2895'	Shale & Lime Shells
2895'	-	2925'	Shale.
2925'	-	2995'	Lime & Shale.
2995'	-	3015'	Shale & Lime
3015'	-	3050'	Lime
3050'	-	3080'	Lime
3080'	-	3120'	Shale & Lime
3120'	-	3310'	Lime & Shale
3310'	-	3315'	Lime
3315'	-	3375'	Lime & Shale
3375'	-	3415'	Lime
3415'	-	3426'	Shale
3426'	-	3447'	Conglomerate
3447'	-	3448'	Lime
3448'	-	3455'	Lime
3455'	-	3495'	Shale
3495'	-	3540'	Conglomerate
3540'	-	3555'	Sand & Shale
3555'	-	3570'	Shale
3570'	-	3610'	Lime & Chert
3610'	-	3620'	Chert & Sand
3620'	-	3671'	Chert & Lime
3671'	-	3681'	Lime
3681'	-	3700'	Lime
3700'	-	3750'	Lime & Shale
3750'	-		TOTAL DEPTH

PLUGGING
 FILE SEC-17 T11S R17W
 BOOK PAGE 100 LINE 29