

API NUMBER. 15-051-22,280-0000

LEASE NAME Mock

WELL NUMBER 6

4290 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 17 TWP. 11S RGE. 17 ~~KCXXX~~(W)

COUNTY Ellis

Date Well Completed 4/23/81

Plugging Commenced 12/11/86

Plugging Completed 12/15/86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Champlin Petroleum Company

ADDRESS 1400 Smith Street, Suite 1500, Houston, TX 77002

PHONE#(713) 654-2758 OPERATORS LICENSE NO. 6417

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District 6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3378' Bottom 3400' T.D. 3500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	251'	none
				5-1/2"	3499'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

SEE BACK OF PAGE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address Hays, Kansas

STATE OF Texas COUNTY OF Harris, ss.

Marilyn Day

(Employee of Operator) or (~~Operator~~) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Marilyn Day

(Address) 1400 Smith Street, Suite 1500

Houston, Texas 77002


SUBSCRIBED AND SWORN TO before me this 5th day of March, 19 87

Sue Burnett RWD
 Notary Public

My Commission Expires: 9-12-87

MAR 11 1987

03-11-87



RU sandline drill and drive CIBP to 3370' to bottom. RU HOWCO to 8-5/8" x 5-1/2" annulus, mix and pump 5 sx Econolite cement and pressure to 500#. Shut annulus in and hook up 5-1/2" csg. Mix and pump 145 sx Econolite cement w/4 sx cottonseed hulls mixed in first 25sx. Pressure csg to 750# and shut well in. Well P&A @ 2:00 pm 12/15/86. Cut off 5-1/2' below ground level. Cap w/2 sx cement. Gilbert Scheck was state plugger on location.

DRILLERS LOG

No. 6 Mock

CASING RECORD:	COMPANY:	Champlin Petroleum Company	DESCRIPTION:
8 5/8" @ 250' w/200 sx cement	CONTRACTOR:	Red Tiger Drilling Company	SE/4 NW/4 NE/4 Sec. 17-T11S-R17W Ellis County, Kansas
5 1/2" @ 3,499' w/200 sx cement	COMMENCED:	January 26, 1981	
TOTAL DEPTH: 3,500'	COMPLETED:	February 3, 1981	ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	254	
Shale & Sand	254	910	
Shale	910	1072	
Anhydrite	1072	1111	
Shale	1111	2250	
Shale & Lime	2250	2970	
Lime	2970	3385	
Arbuckle	3385	3500	
RTD		3500	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 13th day of February, 1981.

Joyce A. Baer
Notary Public

