

RECEIVED  
JUN 06 2002  
KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 5-007-224880000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 2/02

WELL OPERATOR Woolsey Petroleum Corporation KCC LICENSE # 5506  
(owner/company name) (operator's)  
ADDRESS 125 N. Market, Suite 1000 CITY Wichita,

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (620) 886-5605 Ext. 27

LEASE Magnison WELL# 1 SEC. 23 T. 33 R. 13 (East/West)

- NE - NE - SW SPOT LOCATION/QQQQ COUNTY Barber

2310 FEET (in exact footage) FROM S N (circle one) LINE OF SECTION (NOT Lease Line)

2970 FEET (in exact footage) FROM E W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 10.75" SET AT 225' CEMENTED WITH 175 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 5122' CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Attached

ELEVATION 1577 T.D. 5130' PBDT 5050' ANHYDRITE DEPTH 650  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP& 4 sax cement @3750'. Cut csg & spot 50 sax @ 650', 70 sax @ 225' & 15 sax @ 40', use 60/40 + 6% Gel

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carl W. Durr PHONE# (620) 886-5606 Ext. 27

ADDRESS Medicine Lodge, KS City/State KS

PLUGGING CONTRACTOR Clarke Corporation KCC LICENSE # 5160-5105 4/02  
(company name) (contractor's)

ADDRESS Medicine Lodge, KS 67104 PHONE # (620) 886-5665

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 6-10-2002 @ 8:15 AM

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6/4/02 AUTHORIZED OPERATOR/AGENT: Carl W. Durr  
(signature)