



ORIGINAL

Slide Two

CONFIDENTIAL

Operator Name: WOOLSEY OPERATING COMPANY, LLC Lease Name: BELL B Well #: 1  
Sec. 6 Twp. 34 S. R. 11  East  West County: BARBER

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken  Yes  No  
(Attach Additional Sheets)  
Samples Sent to Geological Survey  Yes  No  
Cores Taken  Yes  No  
Electric Log Run  Yes  No  
(Submit Copy)  
List All E. Logs Run:  
 Compensated Neutron Density PE  
 Dual Induction  
 Cement Bond

<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample
Name	Top	Datum
Chase	1856	- 386
Toronto	3716	- 2246
Douglas	3738	- 2268
Swope	4381	- 2911
Hertha	4412	- 2942
Mississippian	4610	- 3140
Viola	4963	- 3493
Simpson	5070	- 3600

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	14 3/4"	10 3/4"	32# / ft	211'	60/40 poz	200	2% gel, 3% cc
Production	7 7/8"	4 1/2"	10.5# / ft	5062'	60/40 poz	50	4% gel, 1/4# Floeal
					Class H	150	10% salt, 10% Gyp, 1/4# Floeal, 6# Kolseal, .8% FL-160

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone (Stalnakar)				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	Mississippian 4624'-4650'	ACID: 2950 gal 10% MIRA	
2	Mississippian 4668'-4696'	FRAC: 554,700 gal treated fr wtr, 195,000# 30/70 sd, 35,000# 16/30 sd & 15,000# 16/30 resin coated sd	

TUBING RECORD Size 2 3/8" Set At 4508' Packer At n/a Liner Run  Yes  No

Date of First, Resumerd Production, SWD or Enhr. 09/26/2008 Producing Method  Flowing  Pumping  Gas Lift  Other (Explain)

Estimated Production Per 24 Hours Oil 5 Bbls. Gas 195 Mcf Water 60 Bbls. Gas-Oil Ratio 39,000 : 1 Gravity n/a

Disposition of Gas METHOD OF COMPLETION Production Interval  Vented  Sold  Used on Lease (If vented, Submit ACO-18.)  Open Hole  Perf.  Dually Comp.  Commingled 4624' - 4696' OA  Other (Specify)



# ALLIED CEMENTING CO., LLC. 32311

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
*Medicine Lodge KS.*

DATE <i>8-1-08</i>	SEC <i>6</i>	TWP <i>34s</i>	RANGE <i>11W</i>	CALLED OUT <i>9:00 PM</i>	ON LOCATION <i>9:30 P</i>	JOB START <i>12:45 AM</i>	JOB FINISH <i>1:15 AM</i>
LEASE <i>Bell B</i>		WELL # <i>1</i>		LOCATION <i>Medicine Lodge KS. 10 1/2 mi south on 281 to Talbot Rd.</i>		COUNTY <i>Barber</i>	STATE <i>KS.</i>
OLD OR NEW (Circle one) <i>NEW</i> <i>44 east 9/5</i>							

CONTRACTOR <i>Fossil Rig #1</i>	OWNER <i>Woolsey Operating</i>
TYPE OF JOB <i>Surface</i>	
HOLE SIZE <i>14 3/4"</i>	T.D. <i>215'</i>
CASING SIZE <i>10 3/4"</i>	DEPTH <i>200'</i>
TUBING SIZE <i>11"</i>	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX <i>300</i>	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG. <i>15'</i>	
PERFS.	
DISPLACEMENT <i>19 1/4 Bbls Freshwater</i>	
EQUIPMENT	

CEMENT			
AMOUNT ORDERED	<i>200 sx Class A + 3% cc + 2% gel</i>		
COMMON	<i>200 A</i>	@ <i>15.45</i>	<i>3090.00</i>
POZMIX		@	
GEL	<i>4</i>	@ <i>20.80</i>	<i>83.20</i>
CHLORIDE	<i>7</i>	@ <i>58.20</i>	<i>407.40</i>
ASC		@	
		@	
		@	

**KCC**  
**NOV 26 2008**  
**CONFIDENTIAL**

PUMP TRUCK # <i>352</i>	CEMENTER <i>Carl Balding</i>
BULK TRUCK # <i>421</i>	HELPER <i>Mike Becker</i>
BULK TRUCK #	DRIVER <i>Adam Arensdorf</i>
BULK TRUCK #	DRIVER

### WELL FILE

Regulatory	Correspondence	
Drig / Comp	Workovers	
Tests / Meters	Operations	
	@	
	@	
	@	
HANDLING	<i>211</i>	@ <i>2.40</i> <i>506.40</i>
MILEAGE	<i>11 x 211 x .10</i>	<i>312.00</i>
	<i>min chrg</i>	TOTAL <i>4399.00</i>

REMARKS:  
*Run 200' 10 3/4 casing + a 11' 8 3/8 Landing Joint. Start 3 Bbls Freshwater mix + pump 200 sx Class A + 3% cc + 2% gel Displace cement w/ 19 1/4 Bbls Leave 15' cement in pipe + shut in. Circulate 75 sx to pit.*

### SERVICE

DEPTH OF JOB	<i>200'</i>	
PUMP TRUCK CHARGE		<i>1018.00</i>
EXTRA FOOTAGE	@	
MILEAGE	<i>11</i>	@ <i>7.00</i> <i>77.00</i>
MANIFOLD	@	
	@	

CHARGE TO: *Woolsey Operating Co.*

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

TOTAL *1095.00*

### PLUG & FLOAT EQUIPMENT

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

**RECEIVED**  
 @ KANSAS CORPORATION COMMISSION  
 @ **NOV 26 2008**  
 @ CONSERVATION DIVISION  
 @ WICHITA, KS  
 TOTAL \_\_\_\_\_

PRINTED NAME *Scott A. Berg*

SIGNATURE *[Signature]*

SALES TAX (If Any) \_\_\_\_\_

TOTAL CHARGES *[Circled]*

DISCOUNT *[Circled]* IF PAID IN 30 DAYS

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

# ALLIED CEMENTING CO., LLC. 32373

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: medicine lodge

DATE <u>8/10/08</u>	SEC. <u>6</u>	TWP. <u>34S</u>	RANGE <u>11W</u>	CALLED OUT <u>6:30 p.m</u>	ON LOCATION <u>7:30 p.m</u>	JOB START <u>5:45 a.m</u>	JOB FINISH <u>1:30 a.m</u>
LEASE <u>Bell B</u>			WELL # <u>1</u>	LOCATION <u>med. lodge. 10 s to tel bot rd.</u>		COUNTY <u>Lincoln</u>	STATE <u>Ks.</u>
OLD OR NEW (Circle one) <u>NEW</u>				<u>1/4 c, slinto</u>			

CONTRACTOR Fossil  
 TYPE OF JOB production  
 HOLE SIZE 7 7/8 T.D. 5175  
 CASING SIZE 4 1/2 DEPTH 5061  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX 1000 MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT 45  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT 80 1/2 Bbls 2% Kcl H<sub>2</sub>O

OWNER Woolsey Oper.

CEMENT  
 AMOUNT ORDERED 75 s x 60.40.4 + 1/4 # flo seal  
150 s x 11 + 10% Gyp Seal + 10% Seal + 1/2 # Kcl Seal + 8%  
Altoth # H seal Ck pro 8 gals

COMMON	<u>45 A</u>	@	<u>15.45</u>	<u>695.25</u>
POZMIX	<u>30</u>	@	<u>8.00</u>	<u>240.00</u>
GEL	<u>3</u>	@	<u>20.80</u>	<u>62.40</u>
CHLORIDE		@		
ASC		@		
<u>150 H</u>		@	<u>16.75</u>	<u>2512.50</u>
<u>Flo Seal 56 #</u>		@	<u>2.50</u>	<u>140.00</u>
<u>Gyp Seal 14</u>		@	<u>29.20</u>	<u>408.80</u>
<u>Salt 28</u>		@	<u>12.00</u>	<u>336.00</u>
<u>Kcl Seal 900 #</u>		@	<u>.89</u>	<u>801.00</u>
<u>FL-160 113 #</u>		@	<u>13.30</u>	<u>1502.90</u>
<u>CIA Pro 8 gals.</u>		@	<u>31.25</u>	<u>250.00</u>
HANDLING	<u>292</u>	@	<u>2.40</u>	<u>700.80</u>
MILEAGE	<u>11 x 292 x .10</u>			<u>321.20</u>
TOTAL				<u>7970.85</u>

**REMARKS:**

Rife on bottom break CIA plug cut & mouse w/  
255x pump 505x on 404 subhead mix 1505x  
H<sub>2</sub>O 10. Stop. Wash pump & lines. release plug.  
Disp w/ 2% Kcl. Seal w/ 253 Bbls. Slow  
rate Run plug 1000 over @ 80 Bbls.  
Plant d. d. w.

**WELL FILE**

Regulatory Correspondence  
 Drg / Comp Workovers  
 Tests / Meters Operations

CHARGE TO: Woolsey Oper.  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**RECEIVED**  
 KANSAS CORPORATION COMMISSION  
 NOV 26 2008

To Allied Cementing Co., LLC  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME MIKE THARP

SIGNATURE Mike Tharp

**SERVICE**

DEPTH OF JOB	<u>5061'</u>		
PUMP TRUCK CHARGE			<u>2295.00</u>
EXTRA FOOTAGE	@		
MILEAGE	<u>11</u>	@	<u>7.00</u> <u>77.00</u>
MANIFOLD	@		
<u>Head Rental</u>	@	<u>113.00</u>	<u>113.00</u>
TOTAL <u>2485.00</u>			

4 1/2" **PLUG & FLOAT EQUIPMENT**

<u>11-Subalizers</u>	@	<u>68.00</u>	<u>748.00</u>
<u>20-Scratchers</u>	@	<u>68.00</u>	<u>1360.00</u>
<u>1-Flt float shoe</u>	@	<u>434.00</u>	<u>434.00</u>
<u>1-Latch Down</u>	@	<u>405.00</u>	<u>405.00</u>
TOTAL <u>2947.00</u>			

SALES TAX (If Any) \_\_\_\_\_  
 TOTAL CHARGES 2947.00  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

**ANY APPLICABLE TAX  
 WILL BE CHARGED  
 UPON INVOICING**

**KCC**  
 NOV 26 2008  
**CONFIDENTIAL**