

ORIGINAL

CONFIDENTIAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Form ACO-1
September 1999
Form Must Be Typed

Handwritten initials and date: KCC, 11/07/08

Handwritten date: 11/03/10

Operator: License # 32825
Name: Pioneer Exploration, LLC
Address: 15603 Kuykendahl Suite 200
City/State/Zip: Houston, Texas 77090
Purchaser: Warren Drilling, LLC
Operator Contact Person: Cynthia B. Gray
Phone: (281) 893-9400 x.259
Contractor: Name: Warren Drilling LLC
License: 33724
Wellsite Geologist: Patrick Deenihan
Designate Type of Completion:
[X] New Well [ ] Re-Entry [ ] Workover
[X] Oil [ ] SWD [ ] SIOW [ ] Temp. Abd.
[ ] Gas [ ] ENHR [ ] SIGW
[ ] Dry [ ] Other (Core, WSW, Expl., Cathodic, etc)
If Workover/Re-entry: Old Well Info as follows:
Operator:
Well Name:
Original Comp. Date: Original Total Depth:
[ ] Deepening [ ] Re-perf. [ ] Conv. to Enhr./SWD
[ ] Plug Back [ ] Plug Back Total Depth
[ ] Commingled [ ] Docket No.
[ ] Dual Completion [ ] Docket No.
[ ] Other (SWD or Enhr.?) [ ] Docket No.
07/08/08 07/17/08 10/06/08
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 06 2008
CONSERVATION DIVISION
WICHITA, KS

API No. 15 - 055-21982-00-00
County: Finney
SE SE NW Sec. 19 Twp. 22 S. R. 33 [ ] East [X] West
2310 feet from S (N) (circle one) Line of Section
2970 feet from (E) (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) (NE) SE NW SW
Lease Name: Garden City "B" Well #: 6-19
Field Name: Damme
Producing Formation: Morrow
Elevation: Ground: 2906 Kelly Bushing: 2919
Total Depth: 4975 Plug Back Total Depth: 4920
Amount of Surface Pipe Set and Cemented at 356 Feet
Multiple Stage Cementing Collar Used? [X] Yes [ ] No
If yes, show depth set 2687 Feet
If Alternate II completion, cement circulated from 4970
feet depth to surface w/ 1050 sx cmt.

Drilling Fluid Management Plan [Handwritten Signature]
(Data must be collected from the Reserve Pit)
Chloride content ppm Fluid volume bbls
Dewatering method used
Location of fluid disposal if hauled offsite:
Operator Name:
Lease Name: License No.:
Quarter Sec. Twp. S. R. [ ] East [ ] West
County: Docket No.:

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Cynthia B. Gray
Title: Field Operations Date: 11/3/2008

Subscribed and sworn to before me this 3rd day of November
20 08

Notary Public: Clark Ordas
Date Commission Expires: 12-13-2010
Clark Ordas
Notary Public, State of Texas
My Commission Expires:
December 13, 2010

KCC Office Use ONLY
[X] Letter of Confidentiality Received
[X] If Denied, Yes [ ] Date:
[X] Wireline Log Received
[X] Geologist Report Received
[ ] UIC Distribution

11/16/08  
6-19

Operator Name: Pioneer Exploration, LLC Lease Name: Garden City "B" Well #: \_\_\_\_\_  
 Sec. 19 Twp. 22 S. R. 33  East  West County: Finney

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken  Yes  No  
 (Attach Additional Sheets)  
 Samples Sent to Geological Survey  Yes  No  
 Cores Taken  Yes  No  
 Electric Log Run  Yes  No  
 (Submit Copy)  
 List All E. Logs Run:

Log Formation (Top), Depth and Datum  Sample  
 Name Top Datum

SEE ATTACHED

*Handwritten:* See my notes 11/07/08

*Handwritten:* X CNL/CDL MEL, DIL, CBL  
 DUAL COMPENSATED POROSITY LOG

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	24	356	Common	225	3% cc w/ 2% gel
Production	7-7/8"	4-1/2"	10.5	4970	C/C-lite/ASC	1050	10% salt, 2% gel, 5# gilsonite; 1/4# flo-seal

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
____ Perforate				
____ Protect Casing				
____ Plug Back TD				
____ Plug Off Zone				


Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	4734-4744, 4758-4763	1500 gal 7 1/2% NEFE w/ 80 balls	4734-4763

TUBING RECORD Size 2-3/8" Set At 4807 Packer At \_\_\_\_\_ Liner Run  Yes  No

Date of First, Resumer Production, SWD or Enhr. 10/6/08 Producing Method  Flowing  Pumping  Gas Lift  Other (Explain)

Estimated Production Per 24 Hours Oil 80 Bbls. Gas 0 Mcf Water 3 Bbls. Gas-Oil Ratio 0 Gravity 28.6

Disposition of Gas \_\_\_\_\_ METHOD OF COMPLETION \_\_\_\_\_ Production Interval \_\_\_\_\_  
 Vented  Sold  Used on Lease (If vented, Submit ACO-18.)  Open Hole  Rod  Plug  Other (Specify) \_\_\_\_\_



Garden City "B" #6-19  
Damme Field  
Finney County  
API. NO. 15-055-21982-00-00

Tops and base of formation penetrated

<u>Name</u>	<u>Top</u>	<u>Datum</u>
Herington	2518	(+401)
Krider	2536	(+383)
Winfield	2698	(+321)
Heeber Shale	3827	(-908)
Lansing	3875	(-956)
Base/Kansas City	4356	(-1437)
Cherokee Shale	4503	(-1584)
Morrow	4696	(-1777)
St. Louis	4776	(-1857)

RECEIVED  
KANSAS CORPORATION COMMISSION  
NOV 06 2008  
CONSERVATION DIVISION  
WICHITA, KS



24 S. Lincoln Street  
P.O. Box 31  
Russell, KS 67665-2906  
Voice: (785) 483-3887  
Fax: (785) 483-5566

# PRIORITY INVOICE

Invoice Number: 114926  
Invoice Date: Jul 8, 2008  
Page: 1

RECEIVED  
JUL 18

Pioneer Exploration, LTD  
P O Box 38  
Spivey, KS 67142-0038

toExp	Garden City B #6-19	Net 30 Days
KS1	Oakley	Jul 8, 2008 8/7/08

QTY	UNIT	DESCRIPTION	PRICE	TOTAL
225.00	MAT	Class A Common	15.45	3,476.25
4.00	MAT	Gel	20.80	83.20
8.00	MAT	Chloride	58.20	465.60
237.00	SER	Handling	2.40	568.80
75.00	SER	Mileage 237 sx @ .09 per sk per mi	23.70	1,777.50
1.00	SER	Surface	1,018.00	1,018.00
54.00	SER	Extra Footage	0.85	45.90
75.00	SER	Mileage Pump Truck	7.00	525.00
1.00	SER	Manifold Surface Head	113.00	113.00
1.00	EQP	Wooden Plug	68.00	68.00

RECEIVED  
KANSAS CORPORATION COMMISSION  
NOV 06 2008  
CONSERVATION DIVISION  
WICHITA, KS

DESCRIPTION Cementing  
Services  
ACCOUNT # 11000-15  
WELL NAME Garden City B #6-19 KS 15904  
AFE# 08050027 J  
DATE 7-18-08 APPROVED \_\_\_\_\_

ALL PRICES ARE NET, PAYABLE  
30 DAYS FOLLOWING DATE OF  
INVOICE. 1 1/2% CHARGED  
THEREAFTER. IF ACCOUNT IS  
CURRENT, TAKE DISCOUNT OF

ONLY IF PAID ON OR BEFORE

Subtotal	8,141.25
Sales Tax	253.77
Total Invoice Amount	8,395.02
Payment/Credit Applied	





**PRIORITY**

**INVOICE**

24 S. Lincoln Street  
P.O. Box 31  
Russell, KS 67665-2906

Voice: (785) 483-3887  
Fax: (785) 483-5566

**RECEIVED**  
JUL 24

Invoice Number: 115103  
Invoice Date: Jul 18, 2008  
Page: 1

Pioneer Exploration, LTD  
P O Box 38  
Spivey, KS 67142-0038

PioExp	Garden City B #6-19	Net 30 Days	
KS1	Oakley	Jul 18, 2008	8/17/08

150.00	MAT	Class C Premium Plus	19.25	2,887.50
525.00	MAT	Lightweight Class A	14.05	7,376.25
2,625.00	MAT	Gilsonite	0.89	2,336.25
119.00	MAT	Flo Seal	2.50	297.50
915.00	SER	Handing	2.40	2,196.00
73.00	SER	Mileage 915 sx @ .10 per sk per mi	91.50	6,679.50
1.00	SER	Production String - Top Stage	1,185.00	1,185.00

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 06 2008  
CONSERVATION DIVISION  
WICHITA, KS

DESCRIPTION cementing  
ACCOUNT # 11688-15  
WELL NAME G.C. B #6 KS 15906  
AFE# 0905D027  
DATE 7-24-08 APPROVED \_\_\_\_\_

ALL PRICES ARE NET, PAYABLE  
30 DAYS FOLLOWING DATE OF  
INVOICE. 1 1/2% CHARGED  
THEREAFTER. IF ACCOUNT IS  
CURRENT, TAKE DISCOUNT OF

ONLY IF PAID ON OR BEFORE

Subtotal	22,958.00
Sales Tax	799.65
Total Invoice Amount	23,757.65
Payment/Credit Applied	

# ALLIED CEMENTING CO., LLC. 31562

REMIT TO - P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Oakley, KS

DATE <u>7/18/08</u>	SEC. <u>19</u>	TWP. <u>22</u>	RANGE <u>33</u>	CALLED OUT	ON LOCATION	JOB START <u>4:30pm</u>	JOB FINISH <u>5:30pm</u>
LEASE <u>Garden City #8</u>	WELL # <u>6-19</u>		LOCATION <u>Biglone - Barlow 1/2 W Sixto</u>		COUNTY <u>Finney</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)							

CONTRACTOR Warren 18

TYPE OF JOB Production String - Top Stage

HOLE SIZE 9.D.

CASING SIZE 4 1/2 - 9 1/2 DEPTH 4970

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL DV DEPTH 2686

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT 42.83'

CEMENT LEFT IN CSG. 42.83'

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER Same

CEMENT AMOUNT ORDERED 192 SKs Class "S"  
650 SKs Lite 5<sup>th</sup> Gilsomite, 1/4 Flo Seal

<u>Class "C" Common</u>	<u>150 SKs</u>	@ <u>19.25</u>	<u>2887.50</u>
POZMIX		@	
GEL		@	
CHLORIDE		@	
ASC		@	<u>7376.25</u>
<u>Lite</u>	<u>925 SKs</u>	@ <u>14.00</u>	<u>12950.00</u>
<u>Gilsomite</u>	<u>2625 lb</u>	@ <u>.890</u>	<u>2336.25</u>
<u>Flo Seal</u>	<u>119 lb</u>	@ <u>2.00</u>	<u>237.00</u>
HANDLING	<u>915 SKs</u>	@ <u>2.40</u>	<u>2196.00</u>
MILEAGE	<u>104 SK/mile</u>		<u>6679.20</u>
TOTAL			<u>21773.00</u>

EQUIPMENT

PUMP TRUCK # <u>437</u>	CEMENTER <u>Alan - Walt</u>
BULK TRUCK # <u>450</u>	HELPER <u>Wayne</u>
BULK TRUCK # <u>394</u>	DRIVER <u>Tony</u>
<u>386</u>	DRIVER <u>John</u>
	<u>Darin</u>

REMARKS:

max 10 SKs Maximal Deck 165% Ret 16lb  
max 500 SKs Lite 5<sup>th</sup> Gilsomite 1/4 Flo Seal, 150 SKs  
Class "C", Wash Pump & liner collar, Displacement  
Displace Plus w/ 4 1/2" water  
Plus loaded @ 1800 DV tool held  
Cement did circulate.

Thank You

CHARGE TO: Pioneer Exploration

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

SERVICE

DEPTH OF JOB	<u>2686'</u>	
PUMP TRUCK CHARGE		<u>1188.00</u>
EXTRA FOOTAGE	@	
RECEIVED <u>73 miles</u>	@	<u>n/c</u>
TOTAL <u>1185.00</u>		

To Allied Cementing Co., LLC.  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Larry Ford

SIGNATURE [Signature]

PLUG & FLOAT EQUIPMENT

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
TOTAL _____		
SALES TAX (If Any) _____		
TOTAL CHARGES _____		
DISCOUNT _____ IF PAID IN 30 DAYS		

NOV 06 2008

CONSERVATION DIVISION  
WICHITA, KS

# ALLIED

**CEMENTING CO., LLC**  
Cementing & Acidizing Services

# PRIORITY INVOICE

24 S. Lincoln Street  
P.O. Box 31  
Russell, KS 67665-2906

Voice: (785) 483-3887  
Fax: (785) 483-5566

Invoice Number: 115102  
Invoice Date: Jul 18, 2008  
Page: 1

**RECEIVED**  
JUL 21

Pioneer Exploration, LTD  
P O Box 38  
Spivey, KS 67142-0038

PioExp	Garden City B #6-19	Net 30 Days	
KS1	Oakley	Jul 18, 2008	8/17/08

QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL
4.00	MAT	Gel	20.80	83.20
200.00	MAT	ASC Class A	18.60	3,720.00
200.00	MAT	Lightweight Class A	14.05	2,810.00
1,000.00	MAT	Gilsonite	0.89	890.00
19.00	MAT	Salt	23.95	455.05
50.00	MAT	Flo Seal	2.50	125.00
460.00	SER	Handling	2.40	1,104.00
73.00	SER	Mileage 460 sx @ .10 per sk per mi	46.00	3,358.00
1.00	SER	Production String - Bottom Stage	2,185.00	2,185.00
73.00	SER	Mileage Pump Truck	7.00	511.00
1.00	SER	Manifold Head Rental	113.00	113.00
1.00	EQP	AFU Float Shoe	434.00	434.00
10.00	EQP	Centralizer	51.00	510.00
3.00	EQP	Basket	169.00	507.00
1.00	EQP	D V Tool	4,219.00	4,219.00
1.00	EQP	Latch Down Assembly	405.00	405.00

RECEIVED  
KANSAS CORPORATION COMMISSION  
NOV 06 2008  
CONSERVATION DIVISION  
WICHITA, KS

DESCRIPTION Cementing  
ACCOUNT # 1600-15  
WELL NAME ACB #1 KS 15906  
AFE # 0805027  
DATE 7-24-08 APPROVED \_\_\_\_\_

ALL PRICES ARE NET, PAYABLE 30 DAYS FOLLOWING DATE OF INVOICE. 1 1/2% CHARGED THEREAFTER. IF ACCOUNT IS CURRENT, TAKE DISCOUNT OF

ONLY IF PAID ON OR BEFORE

Subtotal	21,429.25
Sales Tax	877.81
Total Invoice Amount	22,307.06
Payment/Credit Applied	
<b>Total</b>	<b>22,307.06</b>



# ALLIED CEMENTING CO., LLC. 31561

REMIT TO: P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Oakley, Ks

DATE <u>7/18/08</u>	SEC <u>19</u>	TWP <u>22</u>	RANGE <u>33</u>	CALLED OUT	ON LOCATION <u>6:30 am</u>	JOB START <u>1:00 pm</u>	JOB FINISH <u>2:00 pm</u>
LEASE <u>Card City B</u>	WELL # <u>6-19</u>	LOCATION <u>Bigloma ~ Burlew Rd. W 1/2</u>			COUNTY <u>Fancy</u>	STATE <u>Ks</u>	
OLD OR <u>NEW</u> (Circle one)				<u>S. Into</u>			

CONTRACTOR Warren 18  
 TYPE OF JOB Production string Bottom Stage  
 HOLE SIZE 7 7/8 T.B.  
 CASING SIZE 4 1/2 - 9 1/2 DEPTH 4970  
 TUBING SIZE DEPTH  
 DRILL PIPE DEPTH  
 TOOL D.V. DEPTH 2686  
 PRES. MAX MINIMUM  
 MEAS. LINE SHOE JOINT 42 1/2  
 CEMENT LEFT IN CSG. 42.83  
 PERFS.  
 DISPLACEMENT 40 BBL water, 42 BBL Mud, 82 BBL Total

OWNER Sams  
 CEMENT  
 AMOUNT ORDERED 200 SK 15# 1/4 lb Flo Seal  
200 SK ASC 10# S&T 5" C&S water 20 gal

EQUIPMENT  
 PUMP TRUCK CEMENTER Alan - Wayne  
 # 431 HELPER Walt  
 BULK TRUCK  
 # 386 DRIVER Darrin  
 BULK TRUCK  
 # DRIVER

COMMON	@		
POZMIX	@		
GEL	@	<u>4</u>	<u>20.00</u> <u>83.00</u>
CHLORIDE	@		
ASC	@	<u>200 SK</u>	<u>18.60</u> <u>3720.00</u>
Lite	@	<u>200 SK</u>	<u>14.00</u> <u>2810.00</u>
Cilsonite	@	<u>1000 lb</u>	<u>.894</u> <u>894.00</u>
S&T	@	<u>124 lb</u>	<u>23.99</u> <u>455.05</u>
Flo Seal	@	<u>50 lb</u>	<u>2.50</u> <u>125.00</u>
HANDLING	@	<u>460 SK</u>	<u>2.40</u> <u>1104.00</u>
MILEAGE	@	<u>10.4 SK/mile</u>	<u>33.50</u> <u>335.00</u>
			TOTAL <u>12545.05</u>

REMARKS:  
max 200 SK 4 1/2 1/4 lb Flo Seal 200 SK ASC  
10# S&T 5" C&S water 20 gal. Wash  
Pump & Open Clean, DP place 40 BBL water, 42  
BBL Mud, Plug Landed @ 1500 psi. Float Held,  
Drop DV Tool Open Wait 15 min Open DV  
circulate 2 hrs.

SERVICE

DEPTH OF JOB	<u>4970'</u>
PUMP TRUCK CHARGE	<u>2185.00</u>
EXTRA FOOTAGE	@
MANIFOLD RECEIPT <u>73 miles</u>	@ <u>2.00</u> <u>511.00</u>
MANIFOLD RECEIPT	@ <u>113.00</u>
<b>NOV 06 2008</b>	
CONSERVATION DIVISION WICHITA, KS	
TOTAL <u>2809.00</u>	

CHARGE TO: Pioneer Exploration  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

PLUG & FLOAT EQUIPMENT

<u>4 1/2"</u>		
AFU Floats/Slab	@	<u>434.00</u>
Center/Tracs	@ <u>10</u>	<u>57.00</u> <u>500.00</u>
Baskets	@ <u>3</u>	<u>169.00</u> <u>507.00</u>
DV Tool	@	<u>421.00</u>
Latch Down Ass.	@	<u>405.00</u>
		TOTAL <u>6075.00</u>

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (If Any) \_\_\_\_\_  
 TOTAL CHARGES \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

PRINTED NAME Lacey F. [Signature]  
 SIGNATURE [Signature]