

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

APR 05 1994

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-077-21,032A 0002
C SW NW, SECTION 3 TOWNSHIP 31 RANGE 6W

OPERATOR LICENSE # 6236 3300 FEET FROM S SECTION LINE
4620 FEET FROM E SECTION LINE

OPERATOR MTM PETRO INC
NAME & P O BOX 82
ADDRESS SPIVEY KS 67142

LEASE NAME: STRONG #1 ^{142.96}
COUNTY: HARPER
WELL TOTAL DEPTH: 4399' PB 4337

PIPE: _____

SURFACE CASING: 8-5/8" @ 259'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE
ADDRESS: MEDICINE LODGE KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: JOE CAPPS
COMPANY NAME: SHAWNEE WELL SERVICE PHONE: _____

WERE: PBTD 4337' - 5-1/2" @ 4399' - PERFS 4301'-4303' &
4312'-4316' - SAND BACK TO 4250' & 5 SX - RECOVER PIPE
- 35 SX @ 850' - 35 SX @ 550' - CIRC CMT 310'

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 16:30 DAY: 24 MONTH: 3 YEAR: 1994

ACTUAL PLUGGING REPORT:

PERFS SANDED BACK TO 4232' & CAPPED W/5 SX CMT -
5-1/2" RECOVERED FROM 3089' & PULLED TO 883 & 35 SX CMT
SPOTTED - _____ -
CSG PULLED TO 551.87 WHERE CMT WAS CIRC TO SURF -
REMAINING PIPE PULLED FROM WELLBORE & CMT BROUGHT BACK
TO SURF FROM 302.04.

REMARKS: ALLIED #6302 60/40 4% GEL

I DID OBSERVE THIS PLUGGING.

[Signature]
STEVE VAN GIESON (AGENT)

INVOICED

DATE APR 08 1994

INV. NO. 40275

3-27