

8-28 3/2
API NUMBER 15- 171-20,432 0000

1 070973
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NW, SEC. 29, T 19 S, R 33- W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210
Operator: Lebsack Oil Production, Inc.
Name & Address: P.O. Box 489
Hays, KS 67601

Lease Name Zink Well # 1-29
County Scott 157.30
Well Total Depth 4840 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 313

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 28 Month: 8 Year: 19 91

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4838' w/180 sx cement, PBSD 4700', Perfs at 4475-94'
1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 50 sx cement at 2200',
3rd plug pump 80 sx cement at 1400',
4th plug pump 40 sx cement at 320', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 28 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4425' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped through pipe at 2200' with 50 sx cement,

3rd plug at 1400' with 80 sx cement,

4th plug at 320' with 40 sx cement,

5th plug topped off with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3300' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (I could not observe this plugging.)

Signed Dan Johnson (TECHNICIAN)

DATE 9-13-91
INV. NO. 33110

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1991
CONSERVATION DIVISION
Wichita, Kansas