

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21427-00-00  
Spot: S2NWNW Sec/Twnshp/Rge: 5-34S-8W  
990 feet from N Section Line, 1320 feet from W Section Line  
Lease/Unit Name: ZIMMERMAN C Well Number: 2  
County: HARPER Total Vertical Depth: 5323 feet

Operator License No.: 30535  
Op Name: HARTMAN OIL CO., INC.  
Address: 12950 E. 13TH  
WICHITA, KS 67230

Production Casing Size: 5.5 feet: 5161 250 SX CMT  
Surface Casing Size: 8.625 feet: 293 250 SX CMT

*\$173<sup>00</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/25/2003 12:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: VERNON FRUCHAUT Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: CIBP @ 4300'; 35 sacks @ 1250'; 35 sacks @ 850'; circ 350'.

RECEIVED  
KCC DISTRICT #2  
SEP 26 2003  
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 09/25/2003 5:20 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perms were capped with CIBP at 4300'. The casing was pulled to 1250'; 35 sacks cement was spotted. Pulled casing to 850'; spotted 35 sacks cement. Pull casing to 350' and circulated cement to surface.

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 03 2003  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENT #15279 60/40 POZ MIX 4% GEL

Plugged through: CSG

District: 02

Signed  (TECHNICIAN)

INVOICED  
DATE 10-3-03  
INVT. NO. 2004060576