

8-5

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-20,982

C S \ 2S \ 2SW, SECTION 27 TOWNSHIP 33 RANGE 8W

OPERATOR LICENSE # 5429 330 FEET FROM S SECTION LINE
3960 FEET FROM E SECTION LINE

OPERATOR Bryce F. Hayes Oil and Gas
NAME & P.O. Box 108
ADDRESS Attica, KS 67009

LEASE NAME: Bill Wall #1
COUNTY: Harper
WELL TOTAL DEPTH: 4740'

154.05

P/B 4722

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 331'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Clarke Corp.
ADDRESS: Medicine Lodge KS LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Jeff Stilletto

COMPANY NAME: Clark Corp PHONE: _____

WERE: PBTD 4722', Perf 4653'-61', Sand back to 4600', Rec pipe, 35sx @ 1400', 35sx @ 900', circ to 380'

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 11:30 DAY: 5 MONTH: 8 YEAR: 1993

ACTUAL PLUGGING REPORT:

The Perfs were sanded back to 4500' and capped with 5sx of cmt, the pipe was recovered from 3187' and pulled from the wellbore, Tubing was run to 1423' where 35sx of cmt was spotted, the tubing was pulled 875' where 35sx of cmt was spotted, the tubing was pulled to 389' where cmt was circ to surface, the remaining tubing was pulled from the wellbore and the cmt was topped off.

REMARKS: Allied Cmt 60/40 Poz

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 10 1993

CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 8-17-93

INV. NO. 38366

Steve Van Gieson
Steve Van Gieson (AGENT)

FORM CP-2/3
REV. 3/90