

To: 1 040399  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2-1 15 007 30221-0000  
API NUMBER 15- Drill Completion Date 11/3/65

S/2 SE SE, SEC. 24, T 31 S, R 11 W/E

330 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5105

Lease Name Shepherd Well # 1

Operator: Clarke Corporation

County Barber 146.67

Name & Address P.O. Box 187

Well Total Depth 4513 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 a.m. Day: 1 Month: 2 Year: 1990

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4495' Open hole 4495-4513' Elevation 1720' GL

1st plug sand back to 4445' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11 a.m. Day: 1 Month: 2 Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded back to 4445' and dumped 5 sx cement on top of sand with dump bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 2% gel by B.J. Titan. Recovered 2500' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION 02-07-90 FEB 7 1990

INVOICED observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE FEB 14 1990

INV. NO. 27424