

1 010209

JAN 28 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-N/A 007-30274-0000

C NE NE, SEC. 25, T 31 S, R 11 W/E
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5105

Lease Name Enderud Well # 1

Operator: Clarke Corporation

County Barber 146.25

Name & Address P.O. Box 187,

Well Total Depth 4500 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9 a.m. Day: 28 Month: 1 Year: 19 87

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4487' Open hole - 13"

1st plug sand back to 4425' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 2' sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:30 a.m. Day: 28 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4437' and dumped 5 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Recovered 3800' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED
STATE CORPORATION COMMISSION
observe this plugging.

DATE 2-3-87 FEB 3 1987

Signed Don Ubel
(TECHNICIAN)

INV. NO. 16066
CONSERVATION DIVISION
Wichita, Kansas
02-03-87