

4-050295

11-14

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-167-22,641-00-00

NE SE NE /4 SEC. 27, 13 S, 15 W
3630 feet from S-section line
330 feet from E section line

Operator license# 31464

Lease: D. Dumlér Well # 2

Operator: H & H Production, Inc.

County: Russell 114.66

Address: Box 348
Russell, Kansas 67663
785-483-4939

Well total depth 3528 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 466 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address:

Company to plug at: Hour: A.M. Day: 14 Month: November Year: 1997

Plugging proposal received from: Ted Luebbers

Company: Phone:

Were: Used 60/40 pozmix - 10% gel - and hulls.
8 5/8" set at 466' w/200 sxs cement. 5 1/2" set at 3399' w/125 sxs cement.
Perfs at 3339' - 3342' and 3312' - 3316'.

RECEIVED
NOV 19 1997
11-24-1997

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None

Completed: Hour 12:30 P.M. Day: 14, Month: November, Year: 1997

Actual plugging report: Cleaned out hole to 1082'. Pulled tubing to 800'. Perforated at 1000'. Tied onto tubing - pumped 95 sxs cement and 400# hulls. Cement circulated to surface. Pulled rest of tubing - tied onto backside and squeezed 25 sxs cement and 100# hulls. Max. P.S.I. 400#. S.I.P. 200#. Tied onto 5 1/2" casing - squeezed with 25 sxs cement and 50# hulls. Max. P.S.I. 800#. S.I.P. 200#.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1909 GL

I did / did not observe the plugging.

Mawen Miller
(agent)

INVOICED

DATE DEC 08 1997

INV. NO. 49591