

1052269

STATE CORPORATION COMMISSION

6-18

API NUMBER 15-185-20,759 SE SW NW, SEC. 2, T 21 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 2970 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4290 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ENGLEMAN WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD

OPERATOR LICENSE # 5088

WELL TOTAL DEPTH 3435 111.64 FEET

OPERATOR: DARRAH OIL COMPANY

PRODUCTION CSG: SIZE 4 1/2" FEET 3635'

NAME AND ADDRESS 225 NORTH MARKET SUITE 300

SURFACE CASING: SIZE 8 5/8" FEET 335'

WICHITA, KS 67202-3417

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR D.S.&W. WELL SERVICE, INC. LICENSE NUMBER 6901

ADDRESS P.O. BOX 231, CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 18 MONTH: JUNE YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KENT STRUBE

(COMPANY NAME) D.S.&W. WELL SERVICE, INC. (PHONE) 316-587-3361

WERE: PERFORATIONS @ 3435' ? TUBING FISH AT 375' PACKER STUCK IN HOLE @ 1215'

SAND BOTTOM TO 3380' AND PLACE 4 SX OF CEMENT ON TOP OF THE SAND WITH DUMP BAILOR

RECOVER PIPE AND RUN TUBING AND SPOT PLUGS AS FOLLOWS:

1ST PLUG AT 800' WITH 10 SX OF GEL FOLLOWED BY 50 SX OF CEMENT. 2ND PLUG AT 335' WITH

50 SX OF CEMENT. 40' WITH 10 SX OF CEMENT

RECOMMENDED 60/40 POZMIX 6% GEL PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 18 MONTH: JUNE YEAR: 1998

ACTUAL PLUGGING REPORT FISHED TUBING OUT TO 815' AND COULD NOT GET ANY FURTHER.

PULLED OUT 350' OF 4 1/2" CASING, RAN TUBING TO 814"

CIRCULATED CEMENT FROM 814' TO SURFACE WITH 195 SX OF CEMENT.

TOPPED OF HOLE WITH 20 SX OF CEMENT

RECEIVED STATE CORPORATION COMMISSION 06-29-98 JUN 29 1998

CONSERVATION DIVISION Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED RECOVERED 350' OF 4 1/2" CASING

IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

IF (DID) OBSERVE THIS PLUGGING.

DATE 7-2-98

SIGNED Richard W. Lacey (TECHNICIAN)

FORM CP-2/3

INV. NO. 50859

INVOICED