

To: 6 061487  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

5-12-88  
API NUMBER 15- 167-22,401-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181  
Operator: Donald C. Slawson  
Name & Address 200 Douglas Bldg.  
Wichita, Ks. 67202

SW/4, SEC. 30, T 13 S, R 15 W/4  
330 feet from S section line  
4950 feet from E section line  
Lease Name Nowak Well # G 1  
County Russell 11.31  
Well Total Depth 3425 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 430

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050  
Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 1:00PM Day: 12 Month: May Year: 19 88

Plugging proposal received from Mike Kelso  
(company name) Kelso Casing Pulling Inc. (phone) \_\_\_\_\_

were: Order 150 sks 65/35 Poz 10% Gel 2% Econolite 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:45PM Day: 12 Month: May Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 430' w/250 sks. 4 1/2" set at 3424' w/175 sks.

Top perf at 3111'. Plugged bottom w/sand and 4 sks cement to 3050'. Shot pipe one time and recovered 2200'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 125 sks cement w/300 Psi.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 6 1988  
07-06-1988

Remarks: By Allied  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
observe this plugging.

Signed Gilbert G. Scheck  
(TECHNICIAN)  
Gilbert G. Scheck

DATE 7-8-88  
INV. NO. 21244