

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19000-00-00
Spot: CS2SWSW Sec/Twnshp/Rge: 28-13S-15W
330 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: DUMLER L Well Number: 1
County: RUSSELL Total Vertical Depth: 3380 feet

Operator License No.: 31418
Op Name: NEW GENERATION OIL INC
Address: 2015 E HIGHWAY 40
RUSSELL, KS 67665

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 261 165 SX CMT
Production: Size 5.5 feet: 3379 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/06/2001 10:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: CHARLEY H. TRAPP Company: NEW GENERATION Phone: (785) 483-8515

Proposed Order out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plugging Set wooden plug at 2800' and topped with 5 sxs cement.
Method: Shot off casing at 2200'.
At 2800' packer with 19 joints of tubing left in the hole.

109.85

Plugging Proposal Received By: BRUCE BASYE
Date/Time Plugging Completed: 04/06/2001 1:00 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: JAY PFEIFER

Actual Plugging Report:

MIRU Mike's Testing on 5 1/2".
Set wooden plug at 2800' and topped with 5 sxs cement.
Shot casing lose at 2200'.
Recovered 550' when casing parted.
RIH with tubing to 1800' and pumped 150 sxs with 400# hulls.
Pulled tubing to 950' and spotted 100 sxs with 100# hulls.
Pulled tubing to 290' and circulated cement with 50 sxs.
Tubing P.O.O.H.
Hole full of cement.

INVOICED
DATE 4-11-01
INV. NO. 2001061617

RECEIVED
STATE CORPORATION COMMISSION

APR 11 2001
04-11-2001
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

Form CP-2/3

APR 09 2001

AP

replacement card

H & H PRODUCTION
RUSSELL KS

28-13S-15W
C S/2 SW SW

#1 DUMLER, LEON

site: 1 E OF GORHAM KS
cont: WOODMAN-IANNITTI
card: JERRY GREEN

by: RUSSELL
field: GORHAM EXT (1/4 NE)

API 15-167-19000

if date 01/01/77 spd date 05/05/77 drlg comp 05/11/77 card issued 09/01/77 last revised 12/14/98

ELV: 1903 KB, 1898 GL SMP
 tops.....depth/datum
 TARK.....2537 -634
 TOP.....2794 -891
 LANS.....3066 -1163
 BKC.....3309 -1406
 GORHAM SD.....3320 -1417
 ARB.....3344 -1441
 RTD.....3380 -1477

IP status:

OIL, P 50 BOPD, LKC, INTV NA, 09/01/77
 INFO REL: 12/14/98 - ADDED TOPS, CSG, IP & MISC
 INFO
 NOTE: INFO REL 3/16/88 - WAS OIL WELL - TEMP
 COMP
 CSG: 8-5/8" 261 / 165 SX, 5-1/2" 3379 / 200 SX
 COMMENT: EXACT DATE WELL WAS DRILLED IS
 UNKNOWN; NO PERMIT TO DRILL PERMIT FILED OR
 ISSUED BY KCC IN 1977; FIRST PROD ESTAB 9/77; NO
 INFO FROM GEOL BECAUSE OPER TOOK ALL
 RECORDS; WAS API 15-10G-02000, THEN CHGD 15-167-
 02000, THEN OFFICIALLY TO 15-167-19000 BY KCC

COPYRIGHT 1998
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)