

7-7

To: 6 061540
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167-20301-00-00
NW, SEC. 28, T 13 S, R 15 W/E

4950 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6772

Lease Name Lacey Well # 1

Operator: V. Francis Weigel Oil Co.

County Russell 107.09

Name & Address Box 244

Well Total Depth 3295 feet

Gorham, Ks. 67640

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 205

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 9:00AM Day: 7 Month: July Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) _____

were: Order 125 sks 65/35 Pozmix 10% Gel 2% Econolite 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1988
09-16-1988
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00AM Day: 7 Month: July Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 205' w/cwc sks. 5 1/2" set at 3294' w/125 sks.

Top perf at 3028'. Plugged bottom w/sand and 5 sks cement to 2980'. Shot pipe three times and recovered 2211'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 100 sks cement w/500 Psi.

Remarks: By Allied
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Gilbert G. Scheck
(TECHNICIAN)
Gilbert G. Scheck

INVOICED
DATE 9-21-88
INV. NO. 22346