

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-001-02858-00-00
 NWNWNW Sec/Twp/Rge 24 - 26S - 18E
4760 feet from south section line
5150 feet from east section line

Lease/Well# Witner-Williams WIT11

County Allen

Well Total Depth 825 feet

Production Pipe:	2 Size	Feet	825
------------------	--------	------	-----

AB oil well	XXXX	Gas Well	SWD Well/ Input Well	D & A
-------------	------	----------	----------------------	-------

Surface Casing: 8 Size Feet

Plugging Contractor: K-W Oil Well Service Lic. # 3097

Address: 19450 Ford Road Chanute, Ks 66720

Company to plug at: Hour: Day: 6 Month: 3 2009

Plugging proposal received from: Jim Kepley

Company Name: K-W Oil Phone: 620-433-2178

Were: Clean out and prepare well for plugging and circulate cement to surface

Plugging Proposal Received by: Ryan M. Duling

Plugging attended by Agent:	All	Part	None	XXXXX
-----------------------------	-----	------	------	-------

Operations Completed: Hour: Day: 6 Month: 3 2009

Actual Plugging Report: Ran 1" to 825' inside 2" production pipe. Ran 1" to 325' outside of 2"

production pipe. Washed down the backside to 450'. Circulated cement inside and outside of 2"

production pipe to surface. Pulled both cement strings and topped off. A total of 141 sacks of portland

cement was used to plug this well. The well was cut off below grade and the location was restored.

~~KANSAS CORPORATION COMMISSION~~

MAY 04 2009

Remarks: Control # 20090013-011

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Technician