

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 19874 - 00 - 00
NW NW SW Sec/Twp/Rge Sec 16 T29S R17E
2509 (GPS) feet from south section line
4946 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Lease/Well# Stich South-Winner gps# WIN 01County WilsonOperator: State Of Kansas Fee FundWell Total Depth 850 (est) feetName & Stich South ProjectProduction Pipe: 4.5 Size Feet NA

Address _____

Surface Casing: NA Size Feet NA

AB oil well _____ Gas Well _____

SWD Well/ Input Well E-03946.5 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: _____ Hour: _____ Day: 23 Month: 11 2009Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, Inc Phone: 620-433-7730Were: Clean well bore to TD and fill from btm to top with portland cement.

RECEIVED

DEC 16 2009

KCC WICHITA

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXXOperations Completed: Hour: _____ Day: 23 Month: 11 2009Actual Plugging Report: A string of 1" pipe was lowered to check for obstruction and open hole.

The 1" pipe was removed and the well perforated at 350, 150' and 75'. A 1" cement string was lowered to 850' inside the 4.5" production pipe and the well pumped full of cement. A total of 137 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control # 20090027-001. The gps footages for this well are reasonably close to api#15-205-90236 in RBDMS
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN