

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 19879-00-00
SW NE NE Sec/Twp/Rge Sec 20 T29S R17E
4249 (GPS) feet from south section line
1180 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Stich South-Esslinger gps#BAR04

Operator: State Of Kansas Fee Fund

County Wilson

Well Total Depth 850 (est) feet

Name & Stich South Project

Production Pipe: 4.5 Size Feet NA

Address _____

Surface Casing: NA Size Feet NA

AB oil well XXXXXX Gas Well _____

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 4 Month: 12 2009

Plugging proposal received from: Sam Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Clean well bore to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXX

Operations Completed: Hour: _____ Day: 4 Month: 12 2009

Actual Plugging Report: A 1" pipe was lowered to 600' inside the 4.5" to check for obstruction. The well was then perforated at 600', 300' and 150'. A 1" cement string was lowered to 750' and the well pumped full of cement from btm to top thru this cement string. A total of 65 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control # 20090027-013
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN
KCC WICHITA
RECEIVED
JAN 07 2010