

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 19880-00-00
NW NE NE Sec/Twp/Rge Sec 20 T29S R17E
5078 (GPS) feet from south section line
1243 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Lease/Well# Stich South-Esslinger gps#BAR05County WilsonOperator: State Of Kansas Fee FundWell Total Depth 850 (est) feetName & Stich South ProjectProduction Pipe: 6.25 Size Feet NA

Address _____

Surface Casing: NA Size Feet NAAB oil well XXXXXX Gas Well _____

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: Hour: _____ Day: 4 Month: 12 2009Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, IncPhone: 620-433-7730Were: Clean well bore to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: _____

Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXXOperations Completed: Hour: _____ Day: 4 Month: 12 2009Actual Plugging Report: 5' of 16" surface pipe was set. A 1" cement string was washed down theinside of the 6.25" pipe to 625'. A 1" cement string was washed down the outside of the 6.25" pipe to 400'.The well was then pumped full of cement from btm to top thru these cement strings. A total of 215 sacks of
portland cement were used to plug well. The well was cut off below plow depth and the location restored.Remarks: Control # 20090027-014(If additional description is necessary, use BACK of this form.)I did not observe this plugging.

Signed: _____

Alan M. Dunning
TECHNICIAN

RECEIVED
JAN 07 2010

KCC WICHITA