

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22381-00-00
Spot: NENENE Sec/Twnshp/Rge: 27-28S-4E
4948 feet from S Section Line, 308 feet from E Section Line
Lease Name: FRANK MARTIN Well #: 1
County: BUTLER Total Vertical Depth: 2665 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	212		100 SXS CMT
PROD	5.5	2326		225 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/17/2009 8:00 AM
Plug Co. License No.: 33755 Plug Co. Name: QUALITY PLUS OILFIELD SERVICES, LLC
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 938-2388

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/17/2009 3:45 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:
LAYED DOWN RODS AND TUBING. RIH W/WORKSTRING @ 2150' QUALITY WELL SERVICE MIXED & PUMPED 40 SXS CLASS A 3% CC W/100# OF HULLS AND DISPLACED IN CASING. WAITED 2 HOURS. TAGGED CENEPT @ 1912'. PERFORATED SQUEEZE HOLES IN 5-1/2" CASING @ 250', RIH W/WORKSTRING @ 240', QUALITY WELL SERVICE MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL TO SURFACE. SWEDGED INTO 5-1/2" CASING AND PUMPED 60 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 3:45 PM 7-17-2009. QUALITY WELL SERVICE CEMENT TICKET #2477. TOPPED OFF W/15 SXS CEMENT @ SURFACE.

Perfs:

Top	Bot	Thru	Comments
2238	2239	CSG	
2168	2169	CSG	
2158	2159	CSG	

RECEIVED
AUG 28 2009
KCC WICHITA

Remarks: CONTROL NUMBER ~~2009006-001~~ 20090065001 (Per Ab. Well Database)
Plugged through: TBG

District: 02 Signed: Duane Krueger
(TECHNICIAN)

JK 3