

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20005-00-01
Spot: NWSE Sec/Twnshp/Rge: 29-24S-30W
2546 feet from S Section Line, 2551 feet from E Section Line
Lease Name: DARBY Well #: 1
County: GRAY Total Vertical Depth: 2723 feet

Operator License No.: 100
Op Name: KANSAS CORPORATION COMMISSION
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1150		
SURF	8.625	200		WITH 175 SX CMT
PROD	4.5	2940	0	WITH 650 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/05/2010 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JOEL FLORES Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2600' & 2 SX CMT. BOND LOG & PRESSURE TEST CASING. IF CASING TESTS OUT RUN TBG TO 1150' & PUMP 125 SX CMT. DEPENDING ON BONF LOG PUMP 125 SX CMT DOWN 8" X 5 1/2" ANNULUS. IF CASING DOES NOT TEST OUT RUN TBG & PACKER TO 1100'. PUMP 100 SX CMT. RELEASE PACKER & FILL 4 1/2" WITH CMT. PUMP 125 SX CMT DOWN 8" X 4 1/2" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2010 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG PULLED 107 RODS-TBG STUCK- SHOT 3 TIMES, FREE @ 1293'. PULL TBG. SET CIBP @ 1150'. TEST 4 1/2", PUMP INTO @ 200#. RAN BOND LOG. ESTIMATE TOC @ 970'. 2ND PLUG PERFORATE 4 1/2" WITH 3 HOLES. RUN TBG & PACKER TO 847', ESTABLISH RATE, PUMP 70 SX CMT. DISPLACE TO 750'. PARTIAL RETURNS UP ANNULUS. 3RD PLUG TOOH WITH TBG & PACKER. WAIT ON CMT 1 HOUR. TAG TOC W/SANDLINE @ 890'. TIHWT TO 847'. FILLED CASING WITH 55 SX CMT. CIRCULATED 95 SX CMT UP ANNULUS. 4TH PLUG TOOHWT. FILL 4 1/2" WITH 9 SX CMT. 5TH PLUG PUMP 10 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS.

Perfs:


Top	Bot	Thru	Comments
2690			PERFS ESTIMATE

Remarks: USED CLASS C CMT BY ORR ENTERPRISES. CONTROL # : 20100053001

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
APR 16 2010
KCC DODGE CITY

RECEIVED
APR 21 2010
KCC WICHITA

Form CP-20