

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20237-00-01  
Spot: NWNE Sec/Twnshp/Rge: 23-13S-22W  
4620 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: HOLLAND B Well #: 1  
County: TREGO Total Vertical Depth: 4147 feet

Operator License No.: 31431  
Op Name: BARTON EXPLORATION, INC.  
Address: 3017 E 14TH ST  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	256	0	w/200 sxs cmt
PKR		3400		
PROD	4.5	4126	0	w/175 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/20/2010 1:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: LONNIE BARTON Company: BARTON EXPLORATION, INC. Phone: (785) 483-9136

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 600# hulls.  
4 1/2" production packer stuck at approximately 3400'.  
Bridged off at 800'. Drilled out lots of iron sulfide to 1762'.  
Drilling got very hard and lost fluid in the hole.  
Shoot perfs at 1700' - 950' - 245'.  
DV Tool at 1720' with 425 sxs.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/23/2010 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1750' - pumped 105 sxs cement with 150# hulls.  
Pulled tubing to 1050' - pumped 200 sxs cement with 450# hulls - good circulation of cement.  
Squeezed 4 1/2" casing with 20 sxs cement.  
S.I.P. 200#.  
Tied onto backside - full.

Perfs:

Top	Bot	Thru	Comments
3804			
3697			
3659			


INVOICED  
10-14-2010  
2011060090

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4125.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

RECEIVED

JUL 29 2010

Form CP-2/3

KCC WICHITA

JUL 27 2010

TE: KANSAS COUNTY: TREGO OWWO 23-13S-22W  
D: HOLLAND C NW NE  
R: LARSON OPERATING 4620 FSL 1980 FEL SEC  
L: 1 OWWO HOLLAND "B" WELL CLASS: DO ELEV: 2273 GR  
15-195-20237-0001 STATUS: OIL-WO  
D: 09/08/92 COMP: 10/01/92  
: 4149 LTD: FTD: LANSING-KANSAS CITY PBD:

: 4 1/2 MI SW RIGA, KS

COMP 10/1/92, IPP 13 BOPD PROD ZONE- LANSING 3657-3805  
NO CORES OR DSTS

DRLG COMP 09/11/92

NO: OWWO: OLD INFO: FORMERLY DONALD SLAWSON 1 HOLLAND "B". SPUD  
11/28/72. 8 5/8 @ 254 W/200 SX, 4 1/2 @ 4146 W/175 SX. LOG TOPS: LANSING  
3621, ARBUCKLE 4130, ARBUCKLE 4136. OTD 4149. COMP 1/18/73. IPP 135 BOPD.  
PROD ZONE: LANSING 3657-3805. NEW INFO: TO TEST LANSING 3900

DUCING INTERVAL: PERF (LANSING-KANSAS CITY) 3657-3805 GROSS, TREATMENT  
RPTD

G COMMENTS: CO @ 4147

R ADD: BOX 553, GREAT BEND, KS, 67530 PHONE (316) 792-3664;  
ITR: EXPRESS WELL SRVC

RIGHT 1992 PETROLEUM INFORMATION CORPORATION

DATE 11/19/92 CARD #00004-KS