

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21761-00-00
Spot: SE Sec/Twnshp/Rge: 35-17S-16W
1361 feet from S Section Line, 1315 feet from E Section Line
Lease Name: JUNO Well #: 1
County: RUSH Total Vertical Depth: 3125 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1033		WITH 450 SX CMT
PROD	4.5	3042	0	WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/19/2010 4:30 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: SPOT 50 SX CMT ON BOTTOM. PERFORATE @ 1060' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2010 5:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMP 100# HULLS & 50 SX CMT ON BOTTOM. PERFORATE @ 1060' & PUMPED 290 SX CMT. CIRCULATED 15 SX CMT TO PIT.

Perfs:

Top	Bot	Thru	Comments
3050	3060		

INVOICED
DATE 10-14-2010
INV. NO. 2011060091

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

RECEIVED
AUG 31 2010
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
SEP 07 2010
KCC WICHITA