

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-203-20088-00-01
Spot: SWSESE Sec/Twnshp/Rge: 32-19S-36W
330 feet from S Section Line, 1011 feet from E Section Line
Lease Name: SHIMANEK Well #: 1
County: WICHITA Total Vertical Depth: 4632 feet

Operator License No.: 31093
Op Name: BECKER OIL CORPORATION
Address: PO BOX 1150
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4406		WITH 2 SX CMT
CIBP		4514		
CIBP		4551		
SURF	8.625	335		
PROD	4.5	4360	3492	WITH 100 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/19/2010 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JERRY AILEY Company: BECKER OIL CORPORATION Phone: (580) 765-8788

Proposed Plugging Method: PLUG AT 2300' WITH 50 SX CMT. PLUG AT 1300' WITH 80 SX CMT. PLUG AT 710' WITH 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 6-0' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2010 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4406' WITH 2 SX CMT. 1ST PLUG AT 2305' WITH 50 SX CMT. 2ND PLUG AT 1299' WITH 80 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 356' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4561	4571		
4534	4537		
4455	4464		

INVOICED
DATE 10-14-2010
INV. NO. 2011060092

RECEIVED
SEP 10 2010
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED

AUG 30 2010

KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)