

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20182-00-00
Spot: SENESE Sec/Twnshp/Rge: 24-18S-32W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: GRUBE Well #: 1
County: SCOTT Total Vertical Depth: 4015 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3870		WITH 2 SX CMT
SURF	8.625	420		WITH 325 SX CMT
DVT		2260		WITH 450 SX CMT
PROD	535	4000	0	WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2010 8:30 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: WAYNE GERSTNER Company: BEREXCO LLC Phone: (316) 265-3311

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. RUN TBG TO 2300' & SPOT 25 SX CMT. PULL TBG TO 1500' & SPOT 25 SX CMT. PULL TBG. CASING IS PERFORATED @ 1098' & WILL TRY TO CIRCULATE CMT OUT BACKSIDE. IF NOT THEN PUMP CMT DOWN BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2010 4:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

7/27/10: SET CIBP @ 3870' WITH 2 SX CMT. RAN BOND LOG & FOUND TOC @ 1290'. PERFORATED AT 1098' & GOT AN INJECTION RATE OF 2 1/4 BB PER MINUTE @ 550# SLIGHT BLOW ON BACKSIDE. 7/28/10: RUN TBG TO 2300' & SPOT 25 SX CMT. PULL TBG TO 1500' & PUMP 25 SX CMT. PULL TBG & TIE ONTO CASING & PUMP 190 SX CMT. DID NOT CIRCULATE. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 300#. TIED ONTO BACKSIDE & PUMPED 150 SX CMT. MAXIMUM PRESSURE 300#. SHUT IN PRESSURE 200#.

Perfs:

Top	Bot	Thru	Comments
3955	3957		
3922	3925		

INVOICE
DATE 10-14-2010
INV. NO. 2011060094

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
AUG - 3 2010
KCC DODGE CITY

Signed

Michael J. Maier

(TECHNICIAN) RECEIVED

AUG 10 2010
KCC WICHITA

Form CR-77