

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20269-00-00
Spot: SWNWNESE Sec/Twnshp/Rge: 24-18S-32W
2110 feet from S Section Line, 1190 feet from E Section Line
Lease Name: GRUBE Well #: 2
County: SCOTT Total Vertical Depth: 3999 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: PO BOX 20380
WICHITA, KS 67208

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 432 | | WITH 300 SX CMT |
| DVT | | 2254 | | WITH 550 SX CMT |
| PROD | 5.5 | 3998 | 0 | WITH 750 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2010 6:00 PM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: WAYNE GERSTNER Company: BEREXCO LLC Phone: (316) 265-3311

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. RUN TBG TO 2300' & SPOT 25 SX CMT. PULL TBG TO 1500' & SPOT 25 SX CMT. PULL TBG. CASING IS PERFORATED AT 700' & WILL TRY TO CIRCULATE CMT OUT BACKSIDE. IF NOT THEN PUMP CMT DOWN BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2010 8:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

7/27/10: SET CIBP @ 3620' WITH 2 SX CMT. ~~RAN~~ TEMPERATURE LOG. CMT WAS AT 750'. PERFORATED @ 700'. 7/28/10: RUN TBG TO 2300' & SPOT 25 SX CMT. PULL TBG TO 1500' & PUMP 25 SX CMT. PULL TBG. PUT PACKER ON 2 JOINTS OF TBG & RUN IN CASING. TOOK AN INJECTION RATE OF 2 BBL PER MINUTE AT 800#. PUMP 140 SX CMT. DID NOT CIRCULATE. MAXIMUM PRESSURE 900#. SHUT IN PRESSURE 200#. TIED ONTO BACKSIDE & PUMPED 100 SX CMT. MAXIMUM PRESSURE 200#. SHUT IN PRESSURE 100#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3994 | 3997 | | LKC |

INVOICED
DATE 8-14-2010
INV. NO. 2011060094

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Michael J. Maier
(TECHNICIAN)

RECEIVED
AUG - 3 2010
KCC DODGE CITY

RECEIVED
AUG 10 2010
KCC WICHITA

Form CP-207