

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20313-00-00
Spot: SENWSE Sec/Twnshp/Rge: 24-18S-32W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: GRUBE Well #: 3
County: SCOTT Total Vertical Depth: 4011 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3710		WITH 2 SX CMT
CIBP		3990		
SURF	8.625	429		WITH 300 SX CMT
DVT		2201		WITH 500 SX CMT
PROD	5.5	4008	0	WITH 550 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2010 8:30 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: WAYNE GERSTNER Company: BEREXCO LLC Phone: (316) 772-1155

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. RUN TBG TO 2300' & SPOT 25 SX CMT. PULL TBG TO 1500' & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 75 SX CMT IF POSSIBLE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2010 11:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

7/27/10: SET CIBP @ 3710' WITH 2 SX CMT. RAN TEMPERATURE SURVEY CMT TOP OF 30'. 7/28/10: 1ST PLUG RUN TBG TO 2300' & SPOT 25 SX CMT. 2ND PLUG PULL TBG TO 1500' & PUMP 170 SX CMT. CMT CIRCULATED TO SURFACE. 3RD PLUG PULL TBG & TOP OFF WITH 20 SX CMT. CASING STAYED FULL. 4TH PLUG TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
3958	3961		LANSING B

INVOICED
DATE 10-14-2010
INV. NO. 2011060094

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
AUG - 3 2010
KCC DODGE CITY

Signed

Michael Maier
(TECHNICIAN)

RECEIVED

AUG 10 2010

KCC WICHITA

Form CR-2/3