

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-20905-00-01  
Spot: NWNENE Sec/Twnshp/Rge: 26-22S-38W  
4950 feet from S Section Line, 990 feet from E Section Line  
Lease Name: RICE Well #: 3  
County: KEARNY Total Vertical Depth: 5126 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2500		
SURF	8.625	1848		WITH 700 SX CMT
PROD	4.5	3027	0	WITH 380 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/14/2010 9:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: WAYNE GERSTNER Company: BEREXCO Phone: (316) 772-1155

Proposed Plugging Method: (1) SPOT 50 SACK CEMENT PLUG WITH 200# COTTONSEED HULLS THRU TUBING FROM 2500' - 1800'. (2) PERFORATE 4 HOLES IN 4 1/2" CASING AT 1150'. PUMP 26 SACKS CEMENT DOWN 4 1/2' CASING. LEAVE CASING FULL OF CEMENT. CEMENT: 60/40 POZMIX WITH 4% GEL.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/14/2010 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

CIBP @ 2500'. PUMP 50 SX CMT W/200# HULLS THROUGH TBG AT 2476'. FULL CIRCULATION. PERFORATE @ 1150'. CIRCULATE 4 1/2" & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT WITH 250 SX CMT.


INVOICED  
DATE 10-14-2010  
INV. NO. 2011060095

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED  
AUG - 2 2010  
KCC DODGE CITY

RECEIVED  
AUG 04 2010  
KCC WICHITA