

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02256-00-00
Spot: N2SESW Sec/Twnshp/Rge: 19-14S-13W
4290 feet from N Section Line, 1650 feet from W Section Line
Lease Name: EHRlich Well #: 4
County: RUSSELL Total Vertical Depth: 3025 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	232	0	110 SX
PROD	5.5	2982	0	145 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/16/2010 1:30 PM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 415 sxs 60/40 pozmix - 4% gel - 750# hulls.
Perf: 1050' - 700' - 200'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2010 8:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 1964' - pumped 50 sxs cement - followed with 90 sxs cement with 300# hulls.
Pulled tubing to 999' - pumped 50 sxs cement with 100# hulls - cement circulated.
POOH. Hooked to casing and pumped 60 sxs cement.
Max. P.S.I. 150#.
Cement circulated out the Braden head.

Perfs:

Top	Bot	Thru	Comments
2982	3006		OPEN HOLE
2942	2955		LKC 'C'
2930	2934		LKC 'B'
2907	2916		LKC 'A'
2860	2865		
2794	2797		
2437	2440		
2366	2370		
2330	2332		
2320	2324		
2312	2316		
2294	2296		

INVOICED
DATE: 10-14-2010
INV. NO. 2011060095
RECEIVED
AUG 23 2010

Remarks: ALLIED CEMENTING COMPANY-TICKET #41858.

Plugged through: TBG

KCC WICHITA

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM


AUG 18 2010

CORALENA OIL CO. #1 EHRlich 19-14-13W
 NL SE SW

Contr. _____ RUSSELL County

E 1771 Comm. 4-27-41 Comp. 6-4-41 IP 150 BOPD

Tops	Depth	Datum	Casing
			10" 239
ANHY			5" 2936
TOP	2663		A/3000
LANS	2906		
TD	2937		



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS