

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20772-00-02
Spot: SESWNE Sec/Twnshp/Rge: 34-9S-23W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: LAW B Well #: 5
County: GRAHAM Total Vertical Depth: 4004 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	182	0	165 sx
PROD	4.5	4004	0	150 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/19/2010 10:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 500 sxs 60/40 pozmix - 4% gel - 500# hulls.
Bad casing. Could not get below 2455'.
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2010 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

No upper pipe protection.
Perforated 2 holes at 2025' and 1300'.
Ran tubing to 2450'. Allied pumped 180 sxs 60/40 pozmix - 4% gel.
Pulled to 1280'. Allied pumped 50 sxs cement with 200# hulls.
Pulled tubing to 611'. Allied pumped 85 sxs cement with 250# hulls - circulated cement.
PTOH.
Shut down one hour. Topped 4 1/2" casing with 85 sxs - casing full.
Hooked up to backside and pumped 100 sxs cement with 100#hulls.
Max. P.S.I. 50#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3744	3958		LKC

INVOICED
DATE 10-14-2010
INV. NO. 2011060095

RECEIVED
AUG 23 2010
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

AUG 19 2010