

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21719-00-01
Spot: NENW Sec/Twnshp/Rge: 22-17S-11W
4620 feet from S Section Line, 3300 feet from E Section Line
Lease Name: SOEKEN Well #: 8
County: BARTON Total Vertical Depth: 3353 feet

Operator License No.: 31930
Op Name: BLUE RIDGE PETROLEUM CORPORATI
Address: PO BOX 1913
ENID, OK 73702

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	658	0	w/350 sxs cmt
PROD	5.5	3345	0	w/250 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/08/2010 8:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: RICK POPP Company: BLUE RIDGE PETROLEUM CORPO Phone: (620) 786-5514

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls - 10 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/09/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1500' - 650' - 150'.
Ran tubing to 3000' - pumped 10 sxs gel - followed with 50 sxs cement and 100# hulls.
Pulled tubing to 1500' - pumped 125 sxs cement with 200# hulls.
Pulled tubing to 700' - circulated cement to surface with 75 sxs cement with 100# hulls.
Pulled tubing - tied to casing - pumped 50 sxs cement - circulated cement out surface pipe.
Shut in with 300# P.S.I.

Perfs:

Top	Bot	Thru	Comments
3178	3180		SPF
3146	3150		SPF

INVOICED
DATE 10-14-2010
INV. NO. 2011060097

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4073.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

RECEIVED

SEP 16 2010 Form CP-2/3

KCC WICHITA

SEP 10 2010