

4-050259

12-11

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-21,875-0890
120' W. of
NW NE SW /4 SEC. 15, 11 S, 17 W
2310 feet from S section line
3750 feet from E section line

Operator license# 6239
Operator: Zinszer Oil Company, Inc.
Address: P.O. Box 211
Hays, Kansas 67601
913-625-9448

Lease: Bemis "B" Well # 9
County: Ellis 110.11
Well total depth 3388 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 240 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License#

Address:

Company to plug at: Hour: A.M. Day: 11 Month: December Year: 1996

Plugging proposal received from: Perry Henneman

Company: Phone:

Were: Order 290 sxs 60/40 pozmix - 10% gel - 500# hulls.
8 5/8" set at 240 w/160 sxs. 5 1/2" at 3383' w/150 sxs.
1982 squeezed 590' - 620' with 300 sxs. Dakota 218' - 518'. Anhydrite 1058' - 1094'.
Salt 1405' - 1580'. Elevation 1848'. Open hole.

Rec'd 12-17-96

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour 9:30A.M., Day: 11, Month: December, Year: 1996

Actual plugging report: Perforated at 1625' and 1075'. Tied onto 5 1/2" casing - pumped and squeezed with 250 sxs cement and 500# hulls. Max. P.S.I. 800#. S.I.P. 100#. Tied onto backside and squeezed with 40 sxs cement. Max. P.S.I. 500#. S.I.P. 200#.

Remarks:

Condition of casing(in hole): GOOD BAD Any.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Maurin Miller (agent)

INVOICED
DATE 1-3-97
INV. NO. 472617
12-11 FEB 17 1997