

3 023494

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSASName & BUFFALO IV FEE FUNDAddress PLUGGING PROJECTAB oil well Gas Well X SWD Well/ Input Well Other well as hereinafter indicated: Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.Lic. # 30670Address: P.O. BOX 386, CAHANUTE KS. 66720Company to plug at: Hour: 8:00A.M. Day: 22 Month: 5 2009Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 950' THAT HADBEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPSAL WAS TO CIRCULATE ASMUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

TECHNICIAN

Plugging attended by Agent: All Part None XOperations Completed: Hour: 10:00A.M. Day: 22 Month: 5 2009Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENTWAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2' CASING ATSURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUSTO 600'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE8" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACMENT WASFILLED FROM SURFACE. 210 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED

MAY 29 2009

Remarks: Control # 2009 0003-009

(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN