

4-080183

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-12 API number: 15-051-02188-0002

S/2 SE NW /4 SEC. 17, 11S, 17 W
2970 feet from S section line
3300 feet from E section line

Operator license# 3613

Lease Carmicheal well # 3
ANBCC

Operator: Hallwood Petroleum

County Ellis

Address: 4582 S. Ulster Street
Suite 1700
Denver, Colorado

Well total depth 3401 feet
Conductor Pipe: inch @ feet
Surface pipe 10 3/4 Inch @ 1096 feet

110.53

Aband. oil well ~~X~~, Gas well __, Input well __, SWD __, D & A X

ANBCC

Plugging contractor: Allied Cementing Company License#

Address: 24 S. Lincoln, Russell, Kansas

Company to plug at: Hour: AM Day: 12 Month: March Year: 1996

Plugging proposal received from: Aven Weaverling

Company: Halwood Petroleum phone: 303-850-6257

Were: Perf at 1700', 1125', 500'. Pump 75 sx 60/40 poz, 10% gel with 300# of hulls down 7" casing. Pump 24 sx of gel followed with 120 sx 60/40 poz, 10% gel down 7". Pump 100 sx 60/40 poz, 10% gel down 10 3/4" X 7" annulus. Squeeze 7" casing.

RECEIVED COMM
KANSAS CORP
1996 MAR 19 A 11:41
3-19-96

Plugging Proposal Received by: Bruce Basye
Plugging operations attended by agent? All[XXX], Part[], None[]

Completed: Hour: 11:45, Day: 12, Month: March, Year: 1996

Actual plugging report: Perfed at 1700', 1125', 500'. Pumped 75 sx 60/40 poz, 10% gel with 300# of hulls down 7" casing. Pumped 24 sx of gel followed with 120 sx 60/40 poz, 10% gel down 7". Pumped 100 sx 60/40 poz, 10% gel down 10 3/4" X 7" annulus. Squeeze 7" casing with 80 sx 60/40 poz, 10% gel at 300# maximum, and 200# of shut in.

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X Elevation: 1840 GL

INVOICED

I did [XX] / did not [] observe the plugging.

DATE 3-26-96

INV. NO. 45133

Bruce D. Basye
Bruce D. Basye
(agent)