

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22488-00-00
Spot: NENESW Sec/Twnshp/Rge: 23-33S-13W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease/Unit Name: MAGNISON Well Number: 1
County: BARBER Total Vertical Depth: 5130 feet

Operator License No.: 5506 Conductor Pipe: Size _____ feet: 8 1/2 6.73
Op Name: WOOLSEY PETROLEUM CORPORATION Surface Casing: Size 10.75 feet: 225 WITH 175 SX CMT
Address: 125 N. MARKET, SUITE 1000 Production: Size 4.5 feet: 5122 WITH 225 SX CMT
WICHITA, KS 67202 Liner: Size _____ feet: _____

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/10/2002 8:15 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN DICK Company: WOOLSEY PETROLEUM Phone: (316) 267-4379

Proposed Plugging Method: CIBP @ 3750' & 2 SX CMT ON TOP. 1ST PLUG AT 650' WITH 50 SX CMT. 2ND PLUG AT 260' WITH 70 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/10/2002 9:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 5050'. PERFS AT 3778-82, CIBP @ 4420, 4480-86, CIBP @ 4508, 4511-38, CIBP @ 4800, 4830-39'. SET CIBP @ 3750' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 650' WITH 50 SX CMT. 2ND PLUG AT 260' WITH 70 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

RECEIVED
JUN 17 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3414' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 6-18-02

INV. NO. 2002061971 JUN 12 2002

Form CP-23