

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33409
Name: Charles Jones
Address 1: 2504 Meridian
Address 2: _____
City: Canton State: Ks Zip: 67428 + _____
Contact Person: Charles Jones
Phone: (620) 628-4731
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Mississippi Depth to Top: 2649 Bottom: NR T.D. 2663
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 169-30012-00-00
Spot Description: _____
3304983 Feet from North / South Line of Section
3304967 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Saline
Lease Name: Miller Well #: B-1
Date Well Completed: _____
The plugging proposal was approved on: 6/17/08 (Date)
by: Greg Eaves (KCC District Agent's Name)
Plugging Commenced: 6/17/08
Plugging Completed: 6/17/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Mississippian	Oil & Water	Surface	8-5/8	131	0
		Production	5-1/2	2649	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Fill bottom of 5-1/2" casing with sand to 2563 ft. Dump 5 sacks cement on top of sand with bailer. Fill casing with fresh water. Perforate 5-1/2" casing at 200 ft. Pump down 5-1/2" casing and circulate cement from 200 ft to top in 5-1/2 x 8-5/8 annulus. Top off annulus and casing with cement next day from 6' to 3'. Used 140 sacks cement on top plug.

Plugging Contractor License #: 30280 Name: Sunflower Well Service, Inc
Address 1: P.O. Box 341 Address 2: _____
City: Canton State: Kansas Zip: 67428 + _____
Phone: (620) 654-8342
Name of Party Responsible for Plugging Fees: Charles Jones
State of Kansas County, McPherson, ss.
Terry P Bandy Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Terry P Bandy

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 16 2010

KCC WICHITA

CONSOLIDATED OIL WELL SERVICES.
P.O. BOX 884, CHANUTE, KS 66720
820-431-9210 OR 800-467-8676

MC

 ENTERED

TICKET NUMBER 13747
LOCATION El Dorado # 80
FOREMAN Jim Thomas

TREATMENT REPORT & FIELD TICKET
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
16-17-08	4034	Miller B #1	33	15s	15E	Saline
CUSTOMER Charles Jones			TRUCK #		DRIVER	
MAILING ADDRESS 2504 Meridian			446		Jacob	
CITY Canton			491		Shawn	
STATE Ks			ZIP CODE 67428			

JOB TYPE Plug HOLE SIZE _____ HOLE DEPTH 2663ft. CASING SIZE & WEIGHT 5 1/2"
CASING DEPTH _____ DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety Meeting Rig up to 5 1/2" casing with a 5 1/2" Swedge Pumped 140sk class A down 5 1/2" casing. Puts a 200ft Cement circulated, around the 5 1/2", to surface. Cement circulated in the cellar. Wash up & rig down.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405A	1	PUMP CHARGE	625.00	625.00
5406	82	MILEAGE	3.65	299.30
1104S	140sk	class A	13.50	1890.00
5407A	6.58 Tons	82 miles Bulk Truck	120	647.47
Subtotal				3461.77
SALES TAX				119.01
ESTIMATED TOTAL				3580.84

RECEIVED
NOV 16 2010
KCC WICHITA

282890

AUTHORIZATION _____ TITLE _____ DATE _____