

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-19000-0001

API NUMBER Drilled 10/29/39

LEASE NAME Noni Kollman

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1650 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 18 TWP. 11S RGE. 17 (E) or (W)

COUNTY Ellis

LEASE OPERATOR HALLWOOD PETROLEUM, INC.

ADDRESS P.O. BOX 378111, Denver, CO 80237

PHONE# (303) 850-6257 OPERATORS LICENSE NO. 3613

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 11/20/39

Plugging Commenced 10/14/99

Plugging Completed 10/14/99

The plugging proposal was approved on 10/1/99 (date)

by David P Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3360' Bottom 3363' T.D. 3434'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|-------|---------|--------|------------|
| Arbuckle | Oil | 0 | 40' | 15 1/2" | 40' | 0 |
| | | 0 | 1110' | 10" | 1110' | 0 |
| | | 0 | 3360' | 7" | 3360' | 0 |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Dug out well head. Rigged up Log Teck of KS and perf well at 1000'. Rig up Swift and pumped water establish inj. rate. Pumped 45 sx cement w/ 200# cotton seed hulls followed w/ 80 bbls gelled water followed w/ 120 sx cement. Perf 7" at 150' cement cir. from 10 3/4". Shut in 7" w/ 500#, 12 hr Check. Cement to surface. Restore location. Dennis Hammel, KCC
(If additional description is necessary, use BACK of this form.) present during Plug.

Name of Plugging Contractor Swift Service & Inc. License No. _____

Address P.O. Box 466 Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hallwood Petroleum, Inc.

STATE OF Colorado COUNTY OF Denver, ss.

Nonya K Durham (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Nonya K Durham

(Address) P.O. Box 378111 Denver, CO 80237

SUBSCRIBED AND SWORN TO before me this 27TH day of October, 19 99

RECEIVED
STATE CORPORATION COMMISSION
Rosalind Meyer

My Commission Expires: January 15, 2001

Notary Public
NOV - 3 1999
11-03-99
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 05-88