

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-051-02225-00-00

API NUMBER Drilled 1941

LEASE NAME Noni Kollman

WELL NUMBER 7

       Ft. from S Section Line

       Ft. from E Section Line

SEC. 18 TWP. 11 SRGE. 17 W(E) or (W)

COUNTY Ellis

Date Well Completed 1941

Plugging Commenced 10/14/99

Plugging Completed 10/14/99

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Hallwood Petroleum, Inc.

ADDRESS P.O.Box 378111 Denver, CO 80237

PHONE# (303) 850-6257 OPERATORS LICENSE NO. 3613

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/20/99 (date)

by David P Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached?       

Producing Formation Arbuckle Depth to Top 3343' Bottom 3412' T.D. 3447'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil	0	26'	15 1/2"	26'	0
		0	1105	10"	1105'	0
		0	3343	7"	3343'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.  
Dug out Well Head. Rigged up Express Well Service, Ran 2 3/8" work string to 3396. Rigged up Swift Services and plugged well w/ 80 bbls gel and 50 sx plug on bottom. Pulled tubing to 1100' and filled 7" to surface, pulled tubing, hooked to 10 3/4" could not pump into. Perf 7" at 150' cemented 10 3/4" w/ 5 sx up annulus. Spot 175 sxs of cement & 27 gel & 300# Hulls up 7". Max Pres. 800. 12 hr Check. Cement to Surface. Clean up location and restore. Dennis Hammel, KCC present  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Swift Service & Inc License No.       

Address P.O.Box 466 Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hallwood Petroleum, Inc.

STATE OF Colorado COUNTY OF Denver, ss.

Nonya K Durham (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Nonya K Durham

(Address) P.O.Box 378111 Denver, CO 80237

SUBSCRIBED AND SWORN TO before me this 27<sup>TH</sup> day of October, 19 99

My Commission Expires: January 15, 2001

RECEIVED  
Notary Public  
NOV - 3 1999  
11-03-99