


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 18 Twp. 11s Rge. 17w (E) (W)
Location as "NE/CNW/SW" or footage from lines. C S/2 SWSW
Lease Owner Clinton Oil Company
Lease Name J. Husted #6 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) O:1
Date well completed 12-12 1940
Application for plugging filed 6-27 1974
Application for plugging approved 7-11 1974
Plugging commenced 8/8/74 19
Plugging completed 8/13/74 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 3-18 1972
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3415 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				15 1/2	38'	none
				10	1135	none
				7	3357	2305'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, pushed plug to 3357' with 10' sand and 5 sacks cement.
Shot pipe at 2589', 2509', 2410', 2318', pulled 76 joints. Set rock
bridge at 365 to 355' and ran 7 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1974

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 14th day of August, 1974

My commission expires _____
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

15-051-02218-0000

THE DICKY OIL COMPANY
WICHITA, KANSAS

Husted No. 6

COMMENCED: 11/ 4/40
COMPLETED: 12/12/40

LOCATION: C/8¹/₂SW¹/₄ 18-11-17
ELEVATION:

38' 15 1/2'
1135' 10"
3357' 7"

shale	27
sand	37
post rock	38
shale and shells	191
shale	410
shale and shells	515
iron	545
shale and shells	635
sand	675
red bed	1110
anhydrite	1150
shale and shells	1475
salt	1650
shale and shells	1870
broken lime	1920
lime	2020
broken lime	2250
shale and shells	2812
top Topeka	2812
lime	2828
lime and shale	2870
broken lime	2903
lime	3152
top K.C.Lime	3130
show oil 3115 - 3124	
show oil 3172 - 3177	
show oil 3253 - 3257	
lime	3330
red bed	3352
green shale and chert	3357
top Arbuckle	3357 D.F.
T. D.	3380

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1944
CONSERVATION DIVISION
Wichita, Kansas