

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-02241-0000

LEASE NAME Peavey

WELL NUMBER "A" #1

TYPE OR PRINT  
NOTICE: Fill out completoly  
and return to Cons. Div.  
office within 30 days.

4950 Ft. from S Section Line  
AUB KC

330 Ft. from E Section Line

SEC. 19 TWP. 11 RGE. 17W (E) or (W)

COUNTY Ellis

LEASE OPERATOR Great Eastern Energy

ADDRESS 672 West 4th Hoisington, KS 67544

PHONE (316) 653-2277 OPERATORS LICENSE NO. 9449

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 7-11-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-11-94

The plugging proposal was approved on \_\_\_\_\_ (date)

by Don Butcher (KCC District Agent's Name).

Is ACO-1 filled? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3608'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	243'	none
				5 1/2	3606'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

PLUG JOB ONLY: Perforated well @ 1900'. Ran tubing to 3400' & pumped 35 sks cement. Pull tubing up to 1900', spotted 70 sks cement. Pull tubing to 900', circulate to surface with 65 sks cement. Tied on to surface, pumped 50 sks cement. Shut in @ 150#. Tied on to 5 1/2", pumped 35 sks cement. Shut in @ 300#. 60/40 poz 10% gel. Plugging complete.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Eastern Energy

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 12th day of July, 19 94

Irene Herzberg  
Notary Public

My Commission Expires: \_\_\_\_\_



RECEIVED  
STATE CORPORATION COMMISSION  
JUL 13 1994  
CONSERVATION DIVISION  
Wichita, Kansas

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

15-OSI-02241-0000


COPY

Company MURFIN DRILLING COMPANY  
Farm Peavey "A" No. 1

SEC. 19 T. 11 R. 17W  
NE NE NE

Total Depth. 3608'  
Comm. 9-5-56 Comp. 9-18-56  
Shot or Treated.  
Contractor. Murfin Drilling Company  
Issued. 1-5-57

County Ellis KANSAS



2103' DF

Elevation. \_\_\_\_\_

Production. Dry

CASING:  
8" @243' w/200 sx cem.  
5" @36061/2' w/75 sx cem.

Figures indicate Bottom of Formations.

post rock shale	155
blue shale	243
shale shells	640
sand	735
iron	920
sand	1050
red bed, shale	1356
Anhydrite	1390
shale, shells,	
red bed	1760
salt, shale	1915
shale, lime, shells	2045
lime, shale	3245
lime	3550
lime, shale	3605
lime	3608 RTD

Total Depth

TOPS	
Anhydrite	1356
Topeka	3048
Heebner	3280
Lansing	3323
Simpson	3590
Arbuckle	3604

K. G. S. LIBRARY

RECEIVED  
STATE CORPORATION COM  
JUN 29 1994  
CONSERVATION DIVISION  
Wichita, Kansas