

RECEIVED

APR 29 2002
15-051-01354-00-00
KCC WICHITA

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____
LEASE NAME Peavey A DUBYCC

WELL NUMBER #2
4630' Ft. from S Section Line
330' Ft. from E Section Line

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

SEC. 19 TWP. 11 RGE. 17 (E) or (W)

COUNTY Ellis

Date Well Completed 12/28/56

Plugging Commenced 4/12/02

Plugging Completed 4/12/02

LEASE OPERATOR Great Eastern Energy & Development Corp.

ADDRESS P. O. Drawer 2436, Midland TX 79701

PHONE# (915) 682-1178 OPERATORS LICENSE NO. 9449

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 2002 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation ARB-LKC-Topeka Depth to Top 3240 Bottom 3603 T.D. 3603

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	oil & water	3597'	3603	8 5/8"	383'	0
				5 1/3"	3597'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Ran tubing to 3300', pumped 10 sk. gel & 25 sk cement, pulled tubing to 1500', circulated cement w/ 140 sx, tapped casing w/ 55sx, pumped 55sx down annulus

Name of Plugging Contractor Allied Cementing License No. _____

Address P. O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Eastern Energy & Development Corp.

STATE OF Texas COUNTY OF Midland, ss.

Great Eastern Energy & Development Corp (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) _____

(Address) P. O. Drawer 2436 Midland, TX 79701

SUBSCRIBED AND SWORN TO before me this 24 day of April, 2002

Gwynna B. Crow
Notary Public

My Commission Expires: 1-1-04



OR

MURFIN DRILLING

#2 PEAVEY 'A'

19-11-17W
SW NE NE

Contr. MURFIN DRLG

ELLIS

County

E 2104RB

Comm.

Comp.

1-11-57

IP

250 BOPD

Tops	Depth	Datum
ANH	1353	751
LANS	3315	-1211
ARB	3595	-1191
ID	3598	-1191

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Casing

8" 380

5" 3596

DST 3390-3406/30", 3' MUD,
BHP 350#

DST 3411-18/1 HR, 240' O,
180' WTRY O, 75' WTR, BHP
1080#

DST 3470-90/1 HR, 500' O &
BURNETT MCO, BHP 1000#

TST 65 BOPH,
1500' OB

+	+	+
+	+	+
+	+	+