


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-00754-0080
WELL PLUGGING RECORD

Ellis County, Sec. 19 Twp. 11 Rge. 17W(E) (W)

Location as "NE/CNW/SW" or footage from lines S/2 SE NW
Lease Owner Tomlinson-Kathol, Inc.
Lease Name Peavey Well No. 4
Office Address 414 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9/8/ 19 58
Application for plugging filed 9/8/ 19 58
Application for plugging approved 9/8/ 19 58
Plugging commenced 9/8/ 19 58
Plugging completed 9/8/ 19 58
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	161	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pits jetted and hole filled with heavy mud to 460'
plug @ 460, 20 sacks cement through drill pipe, plug @
150' 20sacks cement through drill pipe, plug @ 40' 10
sacks cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1958 09-11-58
RCW
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Tomlinson-Kathol, Inc.
Address 414 Union Center

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Warren E. Tomlinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Warren E. Tomlinson

(Address)

SUBSCRIBED AND SWORN to before me this 10th day of September, 19 58

Esther Lamore

Notary Public.

My commission expires Jan. 19, 1961

PLUGGING
FILE SEC A.T. 11 R.17W
BOOK PAGE 120 LINE 42

DRILLERS LOG
 TOMLINSON-KATHOL, INC.
 # 4 PEAVEY
 S/2 SE NW, SEC. 19-11S-17W
 ELLIS COUNTY, KANSAS

Contractor - Company Tools

Elevation 1996 KB
 Commenced 8/28/58
 Completed 9/8/58

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	68	Post rock & shale	
68	640	Shale	168" 8 7/8 @ 161' w/125 sks cement
640	728	Iron	
728	780	Shale	
780	980	Sand & shale	
980	1244	Shale & Lime streaks	
1244	1280	Anhydrite	
1280	1853	Shale	
1853	2354	Lime & shale	
2344	3052	Shale	
3052	3228	Lime & Shale	
3228	3544	Lime	
3544	3600	Conglomerate	
3600		Rotary Total Depth	Heebner 3188 Toronto 3210 Lansing 3232 Base K.C. 3473 Conglomerate 3511 D & A

I certify that to the best of my knowledge and belief, the above represents a true and accurate Driller's Log record of the captioned well.

Warren E. Tomlinson
 Warren E. Tomlinson

State of Kansas)
) SS:
 County of Sedgwick)

Subscribed and sworn to before me this 11th day of September, 1958.

Esther Lamone
 Notary Public

My Commission expires Jan. 19, 1961.



RECEIVED
 STATE CORPORATION COMMISSION
 SEP 12 1958

PLUGGING
 FILE SEC 19 T.11 R.17W
 BOOK PAGE 128 LINE 42

CONSERVATION DIVISION