


15-051-19339-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plot

Ellis County, Sec. 19 Twp. 11 Rge. 17 (E) W (W)  
Location as "NE/CNW/SE" or footage from lines SW/NE/SE  
Lease Owner Patton Oil Company  
Lease Name Peavey Well No. 11  
Office Address 672 West Fourth Hoisington, KS 67544  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed August 27, 19. 62  
Application for plugging filed July 23, 19. 82  
Application for plugging approved July 27, 19. 82  
Plugging commenced September 15, 19. 82  
Plugging completed September 15, 19. 82  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production October 20, 19. 78  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation Kansas City Depth to top 3273 Bottom 3275 Total Depth of Well 3534 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	244'	None
Kansas City	Oil & water	3273'	3275'	5 1/2"	3533'	700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 720' feet to surface feet for each plug set.

Allied Cementing Co., pumped 275 sacks of cement into hole through 2 1/2" tubing. Filled hole with cement from 720' to surface. Plugging completed September 15, 1982.

STATE RECEIVED  
SEP 22 1982  
CONSERVATION DIVISION  
WICHITA, KANSAS  
09-22-82

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Allied Cementing Company  
Address Russell, KS

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_ ss.  
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Patton Oil Co by Robert Reed  
672 West 4th Street Hoisington Kansas  
(Address) 67544

SUBSCRIBED AND SWORN TO before me this 21<sup>st</sup> day of September 1982

My commission expires 3/5/85  
Notary Public.

...STENCILED

WELL LOG

ORIGINAL

APR. 6 1963


15-051-19339-0000

COMPANY **Murfin Drilling Company, Etal**  
FARM **PEAVEY UNIT NO. Eleven (11)**

SEC. 19 T. 11S. R. 17 W  
LOC. SW NE SE

RIG. NO. **8**  
TOTAL DEPTH **3534'**  
COMM. **8/19/62** COMP. **8/27/62**  
SHOT OR TREATED **No**  
CONTRACTOR **Murfin Drilling Company**  
ISSUED

COUNTRY **Ellis KANSAS**



CASING  
20 10  
15 8 5/8" 244' with 185 sacks cement  
12 6  
13 5 1/2" 3530' with 125 sacks cement

ELEVATION **1494' Ground**  
**1954' KB**

PRODUCTION **25 BOPD, 2820 WTR**

FIGURES INDICATE BOTTOM OF FORMATIONS

- 246' 12 1/4" Surface Hole
- 490' Shale
- 598' Sand
- 605' Hard Sand
- 630' Hard Sand-Pyrite
- 840' Sand
- 960' Shale & Red Bed
- 1196' Red Bed - Shale
- 1232' Anhydrite
- 1600' Shale & Shells
- 1740' Shale-Salt
- 2120' Shale & Lime
- 2408' Lime-Shale
- 3040' Shale & Lime
- 3475' Lime
- 3517' Shael-Chert-Lime
- 3534' Conglomerate
- 3534' Rotary Total Depth

FORMATION TOPS: *log*

Topeka	2902'	-948
Heebner	3134'	-1180
Toronto	3154'	-1200
Lansing/K. C.	<del>3177'</del> 3177'	<del>-1223</del> -1223
Base/K. C.	3418'	-1464
Cherty Conglomerate	3448'	-1495
Arbuckle	3526'	-1572
Total Depth	<del>3534'</del>	<del>-1580</del>

DST #1 3244'-3300' Open 1 hr. Rec. 380' heavily oil and gas cut mud and 525' muddy oil. IF 89# FF 395# FBHP 975#/20 min.

DST #2 3413'-3460' Open 1 hr. Rec. 330' heavily oil cut mud. IF 67# FF 178# FBHP 372#/20 min.

CORES - NONE

State of Kansas  
County of Sedgwick } ss:

I, Fred M. [Signature] of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the PEAVEY UNIT #11 well.

Subscribed and sworn to before me this 13th day of February 19 63

My Commission Expires: June 14, 1964

*[Signature]*  
*[Signature]*  
NOTARY PUBLIC