

4-042027

15-051-02225-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 1941

N2 NE SE / 4 SEC. 18, 11 S, 17 W  
2310 feet from S section line  
660 feet from E Section line

10-14

Operator license# 3613

Lease: Noni Kollman Well # 7

Operator: Hallwood Petroleum, Inc.

County: Ellis

Address: P.O. Box 378111  
Denver, Colorado 80237

Well total depth 3447 feet  
Conductor Pipe: 15 1/2 inch @ 26 feet  
Surface Pipe: 10 Inch 1105 Feet  
W/N/A sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Swift Service Company License# -

Address: Ness City, Kansas 67560

Company to plug at: Hour: 8:00 A.M. Day: 14 Month: October Year: 1999

Plugging proposal received from: Aven Weaverling

Company: Hallwood Petroleum, Inc. Phone: -

Were: Ordered 200 sxs Mid-Con II cement plus 27 sxs gel and 700# hulls.  
7" casing set at 3343' w/N/A sxs cement. Perfs at 3412' - 3447'.  
Casing squeeze at 565' w/250 sxs cement (1980).

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 2:00 P.M. Day: 14, Month: October Year: 1999

Actual plugging report: R.U. Swift Cementers to tubing set at 3400'. Spotted 15 sxs cement with 300# hulls. Pulled to 3100'. Spotted 27 sxs gel. Pulled to 1100' - spotted 120 sxs cement with 300# hulls to circulate cement at surface. Perf casing at 150'. Squeezed 35 sxs cement down 7" casing to circulate cement out of 10" annulus. 7" casing pressured up to 800# and blew out head. Hooked up to 10" annulus and squeezed 5 sxs down annulus. Estimated 75' of cement down top of 7" casing. Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC X, NO  
Plugged through TUBING X CASING  
Any plug: YES X NO  
Dakota plug: YES X, NO  
Elevation:

I did [ X ] did not observe the plugging.

Dennis J. Hamel (agent)

INVOICED

DATE 11-5  
INV. NO. 60801

RECEIVED  
KANSAS  
DR. COMM  
FORM CP273  
11-04-99