

R

KANSAS

Form CP-3
STATE OF KANSAS
Rev. 6-4-68

STATE CORPORATION COMMISSION

FEB 18 1977

CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135-20571-8000 (of this well)

Operator's Full Name Pickrell Drilling Co.

Complete Address 205 Litwin Bldg., Wichita, Kansas 67202

Lease Name Evel "I" Well No. 1

Location C SE SE Sec. 22 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4575'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 10:30 A Day 17 Month 2 Year 1977

The above well was plugged as follows:

Total Depth 4575' 8 5/8 csg set 266' cwc 150 sk.

5 1/2 csg set 4563' cw 150 sk cmt.

Filled 5 1/2 csg W/sd (4575'-4550') dumped 4 sk cmt W/dump bailer. (4550'-4520')

Cutoff & recovered 1027' of 5 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 15 sk gel & water -followed with 70 sk 50-50 poz 6% gel -displaced with 10 sk gel & water -released 8 5/8 plug & capped with 50 sk 50-50 poz 6% gel & shutin. PP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 2-18-77

INV. NO. 4657-w