

15-167-00251-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SW NE

SEC. 27 TWP. 13 RGE. 15

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Mills

Operator Aladdin ^{Pet} Oil Corp Address 809 Petr Bldg. Wichita, Kans

Field _____ County Russell

Total Depth 3396 Feet.

(Describe briefly the manner in which the well was plugged)

15" at 350', 13" at 620', 10" at 990', 8" at 2625, 7" at 3195, 5 1/2" at 3343',

Pulled 5 1/2", 7" and 8", mudded hole through 10", pulld 10" 13" and 15", filled hole with heavy mud to 280', set rock bridge and 25 sax cement, filled with heavy rotary mud to 25' set rock bridge and 17 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
11-06-1950
NOV 6 - 1950

PLUGGING
FILE SEC 27 T 13 R 15
BOOK PAGE 40 LINE 41

J. J. [Signature]
District Conservation Agent

Date 11-1-50

F